Chapter 51-11C WAC

WASHINGTON STATE ENERGY CODE, APPENDIX CHAPTERS

TABLE OF CONTENTS

Second Printing: September 2013

Appendix A
DEFAULT HEAT LOSS COEFFICIENTS

SECTION A101
GENERAL REQUIREMENTS

A101.1 Scope. The following defaults shall apply to Chapter 4 of both the (RE) and (CE) sections of the IECC. This chapter includes tables of seasonal average heat loss coefficients for specified nominal insulation.

A101.2 Description. These coefficients were developed primarily from data and procedures from the ASHRAE Fundamentals Handbook.

Coefficients not contained in this chapter may be computed using the procedures listed in this reference if the assumptions in the following sections are used, along with data from the sources referenced above.

A101.3 Air films. Default R-values used for air films shall be as follows:

R-Value	Condition
0.17	All exterior surfaces
0.61	Interior horizontal surfaces, heat flow up
0.92	Interior horizontal surfaces, heat flow down
0.68	Interior vertical surfaces

A101.4 Compression of Insulation: Insulation which is compressed shall be rated in accordance with Table A101.4 or reduction in value may be calculated in accordance with the procedures in the ASHRAE Fundamentals Handbook.

A101.5 Building materials. Default R-values used for building materials shall be as shown in Table A101.5.

TABLE A101.4
R-VALUE OF FIBERGLASS BATTS COMPRESSED WITHIN VARIOUS DEPTH CAVITIES

Insulation R-Values at Standard Thickness

Rated R-Value		**82**	**71**	**60**	**49**	**38**	**30**	**22**	**21**	**19**	**15**	**13**	**11**
Standard Thickness, Inches		**26.0**	**22.5**	**19.0**	**15.5**	**12”**	**9.5**	**6.5**	**5.5**	**6**	**3.5**	**3.5**	**3.5**
Nominal Lumber Sizes, Inches	Actual Depth of Cavity, Inches	Insulation R-Values When Installed in a Confined Cavity											
Truss	26.0	82	—	—	—	—	—	—	—	—	—	—	—
Truss	22.5	—	71	—	—	—	—	—	—	—	—	—	—
Truss	19.0	—	—	60	—	—	—	—	—	—	—	—	—
Truss	15.5	—	—	—	49	—	—	—	—	—	—	—	—
Truss	12.0	—	—	—	—	38	—	—	—	—	—	—	—
2x12	11.25	—	—	—	—	37	—	—	—	—	—	—	—
2x10	9.25	—	—	—	—	32	30	—	—	—	—	—	—
2x8	7.25	—	—	—	—	27	26	22	21	19	—	—	—
2x6	5.5	—	—	—	—	—	21	20	21	18	—	—	—
2x4	3.5	—	—	—	—	—	—	14	—	13	15	13	11
	2.5	—	—	—	—	—	—	—	—	—	—	9.8	—
	1.5	—	—	—	—	—	—	—	—	—	—	6.3	6.0

TABLE A101.5
DEFAULT R-VALUES FOR BUILDING MATERIALS

Material	Nominal Size (in.)	Actual Size (in.)	R-Value (Heat Capacity[3])
Air cavity (unventilated), between metal studs at 16 inches on center[a]	-	-	0.79
Air cavity (unventilated), all other depths and framing materials[1]	-	-	0.91
Airfilm, exterior surfaces[2]	-	-	0.17
Airfilm, interior horizontal surfaces, heat flow up[2]	-	-	0.61
Airfilm, interior horizontal surfaces, heat flow down[2]	-	-	0.92
Airfilm, interior vertical surfaces[2]	-	-	0.68
Brick at R-0.12/in. (face brick, 75% solid/25% core area, 130 lbs/ft^3)	4	3.5	0.32 (5.9)
Carpet and rubber pad	-	-	1.23
Concrete at R-0.0625/in., heavyweight (144 lbs/ft^3)	- - - - - -	2 4 6 8 10 12	0.13 (HC-4.8) 0.25 (HC-9.6) 0.38 (HC-14.4) 0.50 (HC-19.2) 0.63 (HC-24.0) 0.75 (HC-28.8)
Concrete masonry units, solid grouted, lightweight (95 lbs/ft^3)	6	-	0.80 (HC-11.4)
Concrete masonry units, solid grouted, normal weight (135 lbs/ft^3)	6	-	0.51 (HC-13.2)
Concrete masonry units, partly grouted, lightweight (95 lbs/ft^3)	6	-	1.33 (HC-6.7)
Concrete masonry units, partly grouted, normal weight (135 lbs/ft^3)	6	-	0.82 (HC-9.0)
Concrete masonry units, solid grouted, lightweight (95 lbs/ft^3)	8	-	1.05 (HC-15.5)
Concrete masonry units, solid grouted, normal weight (135 lbs/ft^3)	8	-	0.69 (HC-17.9)
Concrete masonry units, partly grouted, lightweight (95 lbs/ft^3)	8	-	1.44 (HC-9.6)
Concrete masonry units, partly grouted, normal weight (135 lbs/ft^3)	8	-	0.98 (HC-12.0)
Concrete masonry units, solid grouted, lightweight (95 lbs/ft^3)	10	-	1.30 (HC-19.7)
Concrete masonry units, solid grouted, normal weight (135 lbs/ft^3)	10	-	0.87 (HC-22.6)
Concrete masonry units, partly grouted, lightweight (95 lbs/ft^3)	10	-	1.61 (HC-11.9)
Concrete masonry units, partly grouted, normal weight (135 lbs/ft^3)	10	-	1.11 (HC-14.8)
Concrete masonry units, solid grouted, lightweight (95 lbs/ft^3)	12	-	1.53 (HC-23.9)
Concrete masonry units, solid grouted, normal weight (135 lbs/ft^3)	12	-	1.06 (HC-27.2)
Concrete masonry units, partly grouted, lightweight (95 lbs/ft^3)	12	-	1.75 (HC-14.2)
Concrete masonry units, partly grouted, normal weight (135 lbs/ft^3)	12	-	1.23 (HC-17.5)
Flooring, wood subfloor	-	0.75	0.94
Gypsum board	- -	0.5 0.625	0.45 0.56
Metal deck	-	-	0
Roofing, built-up	-	0.375	0.33
Sheathing, vegetable fiber board, 0.78 in.	-	0.78	2.06
Soil at R-0.104/in.	-	12	1.25
Steel, mild		1	0.0031807
Stucco	-	0.75	0.08

a. There is no credit for cavities that are open to outside air.
b. Air films do not apply to air cavities within an assembly.
c. For heat capacity for concrete and concrete masonry materials with densities other than the values listed in Table A101.5, see Tables A3.1B and A3.1C in ASHRAE/IESNA Standard 90.1.

SECTION A102
CEILINGS

A102.1 General. Table A102.1 lists heat loss coefficients for the opaque portion of exterior ceilings below vented attics, vaulted ceilings and roof decks in units of Btu/h × ft^2 × °F of ceiling.

They are derived from procedures listed in the ASHRAE Fundamentals Handbook. Ceiling U-factors are modified for the buffering effect of the attic, assuming an indoor temperature of 65°F and an outdoor temperature of 45°F.

A102.1.1 Metal framed ceilings. The nominal R-values in Table A103.3.6.2: Effective R-Values for Metal Framing and Cavity Only may be used for purposes of calculating metal framed ceiling section U-factors in lieu of the ASHRAE zone calculation method as provided in Chapter 27 of the ASHRAE Fundamentals Handbook.

Metal building roofs have a different construction and are addressed in Table A102.2.5.

A102.2 Component description. The four types of ceilings are characterized as follows:

A102.2.1 Ceilings below a vented attic. Attic insulation is assumed to be blown-in, loose-fill fiberglass with a K-value of 2.6 h × ft^2 •× °F/Btu per inch. Full bag count for specified R-value is assumed in all cases. Ceiling dimensions for flat ceiling calculations are 45 by 30 feet, with a gabled roof having a 4/12 pitch. The attic is assumed to vent naturally at the rate of 3 air changes per hour through soffit and ridge vents. A void fraction of 0.002 is assumed for all attics with insulation baffles. Standard-framed, unbaffled attics assume a void fraction of 0.008.

Attic framing is either standard or advanced. Standard framing assumes tapering of insulation depth around the perimeter with resultant decrease in thermal resistance. An increased R-value is assumed in the center of the ceiling due to the effect of piling leftover insulation. Advanced framing assumes full and even depth of insulation

TABLE A102.1
DEFAULT U-FACTORS FOR CEILINGS

	Standard Frame	Advanced Frame
Ceilings Below Vented Attics		
Flat	**Baffled**	
R-19	0.049	0.047
R-30	0.036	0.032
R-38	0.031	0.026
R-49	0.027	0.020
R-60	0.025	0.017
Scissors Truss		
R-30 (4/12 roof pitch)	0.043	0.031
R-38 (4/12 roof pitch)	0.040	0.025
R-49 (4/12 roof pitch)	0.038	0.020
R-30 (5/12 roof pitch)	0.039	0.032
R-38 (5/12 roof pitch)	0.035	0.026
R-49 (5/12 roof pitch)	0.032	0.020
Vaulted Ceilings	**16" O.C.**	**24" O.C.**
Vented		
R-19 2x10 joist	0.049	0.048
R-30 2x12 joist	0.034	0.033
R-38 2x14 joist	0.027	0.027
Unvented		
R-30 2x10 joist	0.034	0.033
R-38 2x12 joist	0.029	0.027
R-21 + R-21 2x12 joist	0.026	0.025
Roof Deck	**4x Beams, 48" O.C.**	
R-12.5 2" Rigid insulation	0.064	
R-21.9 3.5" Rigid insulation	0.040	
R-37.5 6" Rigid insulation	0.025	
R-50 8" Rigid insulation	0.019	

extending to the outside edge of exterior walls. Advanced framing does not change from the default value. U-factors for flat ceilings below vented attics with standard framing may be modified with the following table:

Roof Pitch	U-factor for Standard Framing	
	R-30	R-38
4/12	0.036	0.031
5/12	0.035	0.030
6/12	0.034	0.029
7/12	0.034	0.029
8/12	0.034	0.028
9/12	0.034	0.028
10/12	0.033	0.028
11/12	0.033	0.027
12/12	0.033	0.027

Vented scissors truss attics assume a ceiling pitch of 2/12 with a roof pitch of either 4/12 or 5/12. Unbaffled standard framed scissors truss attics are assumed to have a void fraction of 0.016.

A102.2.2 Vaulted ceilings. Insulation is assumed to be fiberglass batts installed in roof joist cavities. In the vented case, at least 1.5 inches between the top of the batts and the underside of the roof sheathing is left open for ventilation in each cavity. A ventilation rate of 3.0 air changes per hour is assumed. In the unvented or dense pack case, the ceiling cavity is assumed to be fully packed with insulation, leaving no space for ventilation.

A102.2.3 Roof decks. Rigid insulation is applied to the top of roof decking with no space left for ventilation. Roofing materials are attached directly on top of the insulation. Framing members are often left exposed on the interior side.

A102.2.4 Metal truss framing. Overall system tested values for the roof/ceiling U_o for metal framed truss assemblies from approved laboratories shall be used, when such data is acceptable to the building official.

Alternatively, the U_o for roof/ceiling assemblies using metal truss framing may be obtained from Tables A102.2.4(1) through A102.2.4(5).

TABLE A102.2.4(1)
STEEL TRUSS[a] FRAMED CEILING U_O

Cavity R-value	Truss Span (ft)												
	12	14	16	18	20	22	24	26	28	30	32	34	36
19	0.1075	0.0991	0.0928	0.0878	0.0839	0.0807	0.0780	0.0757	0.0737	0.0720	0.0706	0.0693	0.0681
30	0.0907	0.0823	0.0760	0.0710	0.0671	0.0638	0.0612	0.0589	0.0569	0.0552	0.0538	0.0525	0.0513
38	0.0844	0.0759	0.0696	0.0647	0.0607	0.0575	0.0548	0.0525	0.0506	0.0489	0.0474	0.0461	0.0449
49	0.0789	0.0704	0.0641	0.0592	0.0552	0.0520	0.0493	0.0470	0.0451	0.0434	0.0419	0.0406	0.0395

TABLE A102.2.4(2)
STEEL TRUSS[a] FRAMED CEILING U_O WITH R-3 SHEATHING

Cavity R-value	Truss Span (ft)												
	12	14	16	18	20	22	24	26	28	30	32	34	36
19	0.0809	0.0763	0.0728	0.0701	0.0679	0.0661	0.0647	0.0634	0.0623	0.0614	0.0606	0.0599	0.0592
30	0.0641	0.0595	0.0560	0.0533	0.0511	0.0493	0.0478	0.0466	0.0455	0.0446	0.0438	0.0431	0.0424
38	0.0577	0.0531	0.0496	0.0469	0.0447	0.0430	0.0415	0.0402	0.0392	0.0382	0.0374	0.0367	0.0361
49	0.0523	0.0476	0.0441	0.0414	0.0393	0.0375	0.0360	0.0348	0.0337	0.0328	0.0319	0.0312	0.0306

TABLE A102.2.4(3)
STEEL TRUSS[a] FRAMED CEILING U_O WITH R-5 SHEATHING

Cavity R-value	Truss Span (ft)												
	12	14	16	18	20	22	24	26	28	30	32	34	36
19	0.0732	0.0697	0.0670	0.0649	0.0633	0.0619	0.0608	0.0598	0.0590	0.0583	0.0577	0.0571	0.0567
30	0.0564	0.0529	0.0502	0.0481	0.0465	0.0451	0.0440	0.0430	0.0422	0.0415	0.0409	0.0403	0.0399
38	0.0501	0.0465	0.0438	0.0418	0.0401	0.0388	0.0376	0.0367	0.0359	0.0351	0.0345	0.0340	0.0335
49	0.0446	0.0410	0.0384	0.0363	0.0346	0.0333	0.0322	0.0312	0.0304	0.0297	0.0291	0.0285	0.0280

TABLE A102.2.4(4)
STEEL TRUSS[a] FRAMED CEILING U_o WITH R-10 SHEATHING

Cavity R-value	Truss Span (ft)												
	12	14	16	18	20	22	24	26	28	30	32	34	36
19	0.0626	0.0606	0.0590	0.0578	0.0569	0.0561	0.0555	0.0549	0.0545	0.0541	0.0537	0.0534	0.0531
30	0.0458	0.0437	0.0422	0.0410	0.0401	0.0393	0.0387	0.0381	0.0377	0.0373	0.0369	0.0366	0.0363
38	0.0394	0.0374	0.0359	0.0347	0.0337	0.0330	0.0323	0.0318	0.0313	0.0309	0.0305	0.0302	0.0299
49	0.0339	0.0319	0.0304	0.0292	0.0283	0.0275	0.0268	0.0263	0.0258	0.0254	0.0251	0.0247	0.0245

TABLE A102.2.4(5)
STEEL TRUSS[a] FRAMED CEILING U_o WITH R-15 SHEATHING

Cavity R-value	Truss Span (ft)												
	12	14	16	18	20	22	24	26	28	30	32	34	36
19	0.0561	0.0550	0.0541	0.0535	0.0530	0.0526	0.0522	0.0519	0.0517	0.0515	0.0513	0.0511	0.0509
30	0.0393	0.0382	0.0373	0.0367	0.0362	0.0358	0.0354	0.0351	0.0349	0.0347	0.0345	0.0343	0.0341
38	0.0329	0.0318	0.0310	0.0303	0.0298	0.0294	0.0291	0.0288	0.0285	0.0283	0.0281	0.0279	0.0278
49	0.0274	0.0263	0.0255	0.0249	0.0244	0.0239	0.0236	0.0233	0.0230	0.0228	0.0226	0.0225	0.0223

Footnotes for Tables A102.2.4(1) through A102.2.4(5)

a. Assembly values based on 24 inch on center truss spacing; 11 Truss member connections penetrating insulation (4 at the eaves, 7 in the interior space); ½ inch drywall ceiling; all truss members are 2x4 "C" channels with a solid web.

b. Ceiling sheathing installed between bottom chord and drywall.

A102.2.5 Metal building roof. Table A102.2.5: The base assembly is a roof where the insulation is compressed when installed beneath metal roof panels attached to the steel structure (purlins). Additional assemblies include continuous insulation, uncompressed and uninterrupted by framing.

U-factors for metal building roofs shall be taken from Table A102.2.5, provided the average purlin spacing is at least 52 inches and the R-value of the thermal spacer block is greater than or equal to the thermal spacer block R-value indicated in Table A107.2.5 for the assembly. It is not acceptable to use the U-factors in Table A102.2.6 if additional insulated sheathing is not continuous.

A102.2.5.1 Single layer. The rated R-value of insulation is for insulation installed perpendicular to and draped over purlins and then compressed when the metal roof panels are attached. A minimum R-3 (R-0.5) thermal spacer block between the purlins and the metal roof panels is required, unless compliance is shown by the overall assembly U-factor.

A102.2.5.2 Double layer. The first rated R-value of insulation is for insulation installed perpendicular to and draped over purlins. The second rated R-value of insulation is for unfaced insulation installed above the first layer and parallel to the purlins and then compressed when the metal roof panels are attached. A minimum R-3 (R-0.5) thermal spacer block between the purlins and the metal roof panels is required, unless compliance is shown by the overall assembly U-factor.

A102.2.5.3 Continuous insulation. For continuous insulation (e.g., insulation boards or blankets), it is assumed that the insulation is installed below the purlins and is uninterrupted by framing members. Insulation exposed to the conditioned space or semi-heated space shall have a facing, and all insulation seams shall be continuously sealed to provide a continuous air barrier.

A102.2.5.4 Liner system (Ls). A continuous membrane is installed below the purlins and uninterrupted by framing members. Uncompressed, unfaced insulation rests on top of the membrane between the purlins. For multilayer installations, the last rated R-value of insulation is for unfaced insulation draped over purlins and then compressed when the metal roof panels are attached. A minimum R-3 (R-0.5) thermal spacer block between the purlins and the metal roof panels is required, unless compliance is shown by the overall assembly U-factor.

A102.2.5.5 Filled cavity. The first rated R-value of insulation is for faced insulation installed parallel to the purlins. The second rated R-value of insulation is for unfaced insulation installed above the first layer, parallel to and between the purlins and compressed when the metal roof panels are attached. The facer of the

first layer of insulation is of sufficient width to be continuously sealed to the top flange of the purlins and to accommodate the full thickness of the second layer of insulation. A supporting structure retains the bottom of the first layer at the prescribed depth required for the full thickness of the second layer of insulation being installed above it. A minimum R-5 (R-0.9) thermal spacer block between the purlins and the metal roof panels is required, unless compliance is shown by the overall assembly U-factor.

A102.2.6 Roofs with insulation entirely above deck (uninterrupted by framing). Table A102.2.6: The base assembly is continuous insulation over a structural deck. Added insulation is continuous and uninterrupted by framing. For the insulation, the first column lists the R-value for continuous insulation with a uniform thickness; the second column lists the comparable area-weighted average R-value for continuous insulation provided that the insulation thickness is never less than R-5 (except at roof drains) and that the slope is no greater than 1/4 inch per foot.

SECTION A103
ABOVE GRADE WALLS

A103.1 General. The tables in this section list heat loss coefficients for the opaque portion of above-grade wood stud frame walls, metal stud frame walls and concrete masonry walls (Btu/h × ft^2 × °F). They are derived from procedures listed in the ASHRAE Fundamentals Handbook. For intermediate floor slabs which penetrate the insulated wall, use the concrete wall U-factors in Table A103.3.7.1(1).

Insulation is assumed to uniformly fill the entire cavity and to be installed as per manufacturer's directions. All walls are assumed to be finished on the inside with 1/2 inch gypsum wallboard, and on the outside with either beveled wood siding over 1/2 inch plywood sheathing or with 5/8 inch T1-11 siding. Insulated sheathing (either interior or exterior) is assumed to cover the entire opaque wall surface, except where modified in accordance with footnote h to Table C402.1.1.

Metal building walls have a different construction and are addressed in Table A103.3.6.3.

A103.2 Framing description. For wood stud frame walls, three framing types are considered and defined as follows:

A103.2.1 Standard. Studs framed on 16 inch centers with double top plate and single bottom plate. Corners use three studs and each opening is framed using two studs. Headers consist of double 2x or single 4x material with an air space left between the header and the exterior sheathing. Interior partition wall/exterior wall intersections use two studs in the exterior wall.

Standard framing weighting factors:

Studs and plates	0.19
Insulated cavity	0.77
Headers	0.04

A103.2.2 Intermediate. Studs framed on 16 inch centers with double top plate and single bottom plate. Corners use two studs or other means of fully insulating corners, and each opening is framed by two studs. Headers consist of double 2x material with R-10 insulation. Interior partition wall/exterior wall intersections are fully insulated in the exterior wall.

Intermediate framing weighting factors:

Studs and plates	0.18
Insulated cavity	0.78
Headers	0.04

A103.2.3 Advanced. Studs framed on 24 inch centers with double top plate and single bottom plate. Corners use two studs or other means of fully insulating corners, and one stud is used to support each header. Headers consist of double 2x material with R-10 insulation. Interior partition wall/exterior wall intersections are fully insulated in the exterior wall.

Advanced framing weighting factors:

Studs and plates	0.13
Insulated cavity	0.83
Headers	0.04

A103.3 Component description. Default coefficients for the following types of walls are listed: Single-stud walls, strap walls, double-stud walls, log walls, stress-skin panels, metal stud walls, and metal building walls.

A103.3.1 Single-stud wall. Tables A103.3.1(1) through A103.3.1(8): Assumes either 2 x 4 or 2 x 6 studs framed on 16 or 24 inch centers. Headers are solid for 2 x 4 walls and double 2x for 2 x 6 walls, with either dead-air or rigid-board insulation in the remaining space.

TABLE A102.2.5
DEFAULT U-FACTORS FOR METAL BUILDING ROOFS

Insulation System	Rated R-Value of Insulation	Overall U-Factor for Entire Base Roof Assembly	Overall U-Factor for Assembly of Base Roof Plus Continuous Insulation (uninterrupted by framing) Rated R-Value of Continuous Insulation					
			R-6.5	R-13	R-19.5	R-26	R-32.5	R-39
Standing Seam Roofs with Thermal Spacer Blocks[a,b]								
Single Layer	None	1.280	0.137	0.073	0.049	0.037	0.030	0.025
	R-10	0.115	0.066	0.046	0.035	0.029	0.024	0.021
	R-11	0.107	0.063	0.045	0.035	0.028	0.024	0.021
	R-13	0.101	0.061	0.044	0.034	0.028	0.024	0.020
	R-16	0.096	0.059	0.043	0.033	0.027	0.023	0.020
	R-19	0.082	0.053	0.040	0.031	0.026	0.022	0.020
Double Layer	R-10 .+ R-10	0.088	0.056	0.041	0.032	0.027	0.023	0.020
	R-10 .+ R-11	0.086	0.055	0.041	0.032	0.027	0.023	0.020
	R-11 .+ R-11	0.085	0.055	0.040	0.032	0.026	0.023	0.020
	R-10 .+ R-13	0.084	0.054	0.040	0.032	0.026	0.023	0.020
	R-11 .+ R-13	0.082	0.053	0.040	0.032	0.026	0.022	0.020
	R-13 .+ R-13	0.075	0.050	0.038	0.030	0.025	0.022	0.019
	R10 .+ R-19	0.074	0.050	0.038	0.030	0.025	0.022	0.019
	R-11 .+ R-19	0.072	0.049	0.037	0.030	0.025	0.022	0.019
	R-13 .+ R-19	0.068	0.047	0.036	0.029	0.025	0.021	0.019
	R-16 .+ R-19	0.065	0.046	0.035	0.029	0.024	0.021	0.018
	R-19 .+ R-19	0.060	0.043	0.034	0.028	0.023	0.020	0.018
Liner System	R-19 .+ R-11	0.035						
	R-25 .+ R-11	0.031						
	R-30 .+ R-11	0.029						
	R-25 .+ R-11 .+ R-11	0.026						
Filled Cavity with Thermal Spacer Blocks[c]								
	R-10 .+ R-19	0.057	0.042	0.033	0.027	0.023	0.020	0.018
Standing Seam Roofs without Thermal Spacer Blocks								
Liner System	R-19 .+ R-11	0.040						
Thru-Fastened Roofs without Thermal Spacer Blocks								
Single Layer	R-10	0.184						
	R-11	0.182						
	R-13	0.174						
	R-16	0.157						
	R-19	0.151						
Liner System	R-19 .+ R-11	0.044						

(Multiple R-values are listed in order from inside to outside)

a. A standing seam roof clip that provides a minimum 1.5 in. distance between the top of the purlins and the underside of the metal roof panels is required.
b. A minimum R-3 thermal spacer block is required.
c. A minimum R-5 thermal spacer block is required.

TABLE A102.2.6
ASSEMBLY U-FACTORS FOR ROOFS WITH INSULATION ENTIRELY ABOVE DECK (UNINTERRUPTED BY FRAMING)

Rated R-Value of Insulation Alone: Minimum Throughout, Unsloped	Rated R-Value of Insulation Alone: Average (R-5 minimum), Sloped (1/4 inch per foot maximum)	Overall U-Factor for Entire Assembly
R-0	Not Allowed	U-1.282
R-1	Not Allowed	U-0.562
R-2	Not Allowed	U-0.360
R-3	Not Allowed	U-0.265
R-4	Not Allowed	U-0.209
R-5	Not Allowed	U-0.173
R-6	R-7	U-0.147
R-7	R-8	U-0.129
R-8	R-9	U-0.114
R-9	R-10	U-0.102
R-10	R-12	U-0.093
R-11	R-13	U-0.085
R-12	R-15	U-0.078
R-13	R-16	U-0.073
R-14	R-18	U-0.068
R-15	R-20	U-0.063
R-16	R-22	U-0.060
R-17	R-23	U-0.056
R-18	R-25	U-0.053
R-19	R-27	U-0.051
R-20	R-29	U-0.048
R-21	R-31	U-0.046
R-22	R-33	U-0.044
R-23	R-35	U-0.042
R-24	R-37	U-0.040
R-25	R-39	U-0.039
R-26	R-41	U-0.037
R-27	R-43	U-0.036
R-28	R-46	U-0.035
R-29	R-48	U-0.034
R-30	R-50	U-0.032
R-35	R-61	U-0.028
R-40	R-73	U-0.025
R-45	R-86	U-0.022
R-50	R-99	U-0.020
R-55	R-112	U-0.018
R-60	R-126	U-0.016

TABLE A103.3.1(1)
2 x 4 Single Wood Stud: R-11 Batt

NOTE:
Nominal Batt R-value:
R-11 at 3.5 inch thickness

Installed Batt R-value:
R-11 in 3.5 inch cavity

Siding Material/Framing Type				
R-value of Foam Board	Lapped Wood		T1-11	
	STD	ADV	STD	ADV
0	0.088	0.084	0.094	0.090
1	0.080	0.077	0.085	0.082
2	0.074	0.071	0.078	0.075
3	0.069	0.066	0.072	0.070
4	0.064	0.062	0.067	0.065
5	0.060	0.058	0.063	0.061
6	0.056	0.055	0.059	0.057
7	0.053	0.052	0.055	0.054
8	0.051	0.049	0.052	0.051
9	0.048	0.047	0.050	0.049
10	0.046	0.045	0.047	0.046
11	0.044	0.043	0.045	0.044
12	0.042	0.041	0.043	0.042

TABLE A103.3.1(2)
2 x 4 Single Wood Stud: R-13 Batt

NOTE:
Nominal Batt R-value:
R-13 at 3.63 inch thickness

Installed Batt R-value:
R-12.7 in 3.5 inch cavity

Siding Material/Framing Type				
R-value of Foam Board	Lapped Wood		T1-11	
	STD	ADV	STD	ADV
0	0.082	0.078	0.088	0.083
1	0.075	0.072	0.080	0.076
2	0.069	0.066	0.073	0.070
3	0.065	0.062	0.068	0.065
4	0.060	0.058	0.063	0.061
5	0.057	0.055	0.059	0.057
6	0.053	0.052	0.056	0.054
7	0.051	0.049	0.052	0.051
8	0.048	0.047	0.050	0.048
9	0.046	0.045	0.047	0.046
10	0.044	0.043	0.045	0.044
11	0.042	0.041	0.043	0.042
12	0.040	0.039	0.041	0.040

TABLE A103.3.1(3)
2 x 4 Single Wood Stud: R-15 Batt

NOTE:
Nominal Batt R-value:
R-15 at 3.5 inch thickness

Installed Batt R-value:
R-15 in 3.5 inch cavity

R-value of Foam Board	Siding Material/Framing Type			
	Lapped Wood		T1-11	
	STD	ADV	STD	ADV
0	0.076	0.071	0.081	0.075
1	0.069	0.065	0.073	0.069
2	0.064	0.061	0.068	0.069
3	0.060	0.057	0.063	0.059
4	0.056	0.053	0.059	0.056
5	0.053	0.051	0.055	0.052
6	0.050	0.048	0.052	0.050
7	0.047	0.046	0.049	0.047
8	0.045	0.044	0.047	0.045
9	0.043	0.042	0.044	0.043
10	0.041	0.040	0.042	0.041
11	0.039	0.038	0.041	0.039
12	0.038	0.037	0.039	0.038

TABLE A103.3.1(4)
2 x 6 Single Wood Stud: R-19 Batt

NOTE:
Nominal Batt R-value:
R-19 at 6 inch thickness

Installed Batt R-value:
R-18 in 5.5 inch cavity

R-value of Foam Board	Siding Material/Framing Type					
	Lapped Wood			T1-11		
	STD	INT	ADV	STD	INT	ADV
0	0.062	0.058	0.055	0.065	0.061	0.058
1	0.058	0.055	0.052	0.060	0.057	0.055
2	0.054	0.052	0.050	0.056	0.054	0.051
3	0.051	0.049	0.047	0.053	0.051	0.049
4	0.048	0.046	0.045	0.050	0.048	0.046
5	0.046	0.044	0.043	0.048	0.046	0.044
6	0.044	0.042	0.041	0.045	0.044	0.042
7	0.042	0.040	0.039	0.043	0.042	0.040
8	0.040	0.039	0.038	0.041	0.040	0.039
9	0.038	0.037	0.035	0.039	0.038	0.037
10	0.037	0.036	0.035	0.038	0.037	0.036
11	0.036	0.035	0.034	0.036	0.035	0.035
12	0.034	0.033	0.033	0.035	0.034	0.033

TABLE A103.3.1(5)
2 x 6 Single Wood Stud: R-21 Batt

NOTE:
Nominal Batt R-value:
R-21 at 5.5 inch thickness

Installed Batt R-value:
R-21 in 5.5 inch cavity

R-value of Foam Board	Siding Material/Framing Type					
	Lapped Wood			T1-11		
	STD	INT	ADV	STD	INT	ADV
0	0.057	0.054	0.051	0.060	0.056	0.053
1	0.054	0.051	0.048	0.056	0.053	0.050
2	0.050	0.048	0.045	0.052	0.050	0.047
3	0.048	0.045	0.043	0.049	0.047	0.045
4	0.045	0.043	0.041	0.047	0.045	0.043
5	0.043	0.041	0.040	0.044	0.042	0.041
6	0.041	0.039	0.038	0.042	0.041	0.039
7	0.039	0.038	0.036	0.040	0.039	0.037
8	0.038	0.036	0.035	0.039	0.037	0.036
9	0.036	0.035	0.034	0.037	0.036	0.035
10	0.035	0.034	0.033	0.036	0.035	0.033
11	0.033	0.033	0.032	0.034	0.033	0.032
12	0.032	0.031	0.031	0.033	0.032	0.031

TABLE A103.3.1(6)
2 x 6 Single Wood Stud: R-22 Batt

NOTE:
Nominal Batt R-value:
R-22 at 6.75 inch thickness

Installed Batt R-value:
R-20 in 5.5 inch cavity

R-value of Foam Board	Siding Material/Framing Type					
	Lapped Wood			T1-11		
	STD	INT	ADV	STD	INT	ADV
0	0.059	0.055	0.052	0.062	0.058	0.054
1	0.055	0.052	0.049	0.057	0.054	0.051
2	0.052	0.049	0.047	0.054	0.051	0.048
3	0.049	0.046	0.044	0.050	0.048	0.046
4	0.046	0.044	0.042	0.048	0.046	0.044
5	0.044	0.042	0.041	0.045	0.043	0.042
6	0.042	0.040	0.039	0.043	0.042	0.040
7	0.040	0.039	0.037	0.041	0.040	0.038
8	0.038	0.037	0.036	0.039	0.038	0.037
9	0.037	0.036	0.035	0.038	0.037	0.035
10	0.035	0.034	0.033	0.036	0.035	0.034
11	0.034	0.033	0.032	0.035	0.034	0.033
12	0.033	0.032	0.031	0.034	0.033	0.032

TABLE A103.3.1(7)
2 x 6 Single Wood Stud: Two R-11 Batts

NOTE:
Nominal Batt R-value:
R-22 at 7 inch thickness

Installed Batt R-value:
R-18.9 in 5.5 inch cavity

R-value of Foam Board	Siding Material/Framing Type					
	Lapped Wood			T1-11		
	STD	INT	ADV	STD	INT	ADV
0	0.060	0.057	0.054	0.063	0.059	0.056
1	0.056	0.053	0.051	0.059	0.056	0.053
2	0.053	0.050	0.048	0.055	0.052	0.050
3	0.050	0.048	0.046	0.052	0.049	0.047
4	0.047	0.045	0.044	0.049	0.047	0.045
5	0.045	0.043	0.042	0.046	0.045	0.043
6	0.043	0.041	0.040	0.044	0.043	0.041
7	0.041	0.040	0.038	0.042	0.041	0.039
8	0.039	0.038	0.037	0.040	0.039	0.038
9	0.038	0.037	0.036	0.039	0.038	0.036
10	0.036	0.035	0.034	0.037	0.036	0.035
11	0.035	0.034	0.033	0.036	0.035	0.034
12	0.034	0.033	0.032	0.034	0.034	0.033

TABLE A103.3.1(8)
2 x 8 Single Stud: R-25 Batt

NOTE:
Nominal Batt R-value:
R-25 at 8 inch thickness

Installed Batt R-value:
R-23.6 in 7.25 inch cavity

R-value of Foam Board	Siding Material/Framing Type					
	Lapped Wood			T1-11		
	STD	INT	ADV	STD	INT	ADV
0	0.051	0.047	0.045	0.053	0.049	0.046
1	0.048	0.045	0.043	0.049	0.046	0.044
2	0.045	0.043	0.041	0.047	0.044	0.042
3	0.043	0.041	0.039	0.044	0.042	0.040
4	0.041	0.039	0.037	0.042	0.040	0.038
5	0.039	0.037	0.036	0.040	0.038	0.037
6	0.037	0.036	0.035	0.038	0.037	0.036
7	0.036	0.035	0.033	0.037	0.035	0.034
8	0.035	0.033	0.032	0.035	0.034	0.033
9	0.033	0.032	0.031	0.034	0.033	0.032
10	0.032	0.031	0.030	0.033	0.032	0.031
11	0.031	0.030	0.029	0.032	0.031	0.030
12	0.030	0.029	0.028	0.031	0.030	0.029

A103.3.2 Strap wall. Table A103.3.2: Assumes 2 x 6 studs framed on 16 or 24 inch centers. 2 x 3 or 2 x 4 strapping is run horizontally along the interior surface of the wall to provide additional space for insulation.

A103.3.3 Double stud wall. Tables A103.3.3(1) and A103.3.3(2): Assumes an exterior structural wall and a separate interior, nonstructural wall. Insulation is placed in both wall cavities and in the space between the two walls. Stud spacing is assumed to be on 24 inch centers for both walls.

A103.3.4 Log wall. See Table A103.3.4.

A103.3.5 Stress-skin panel. See Table A103.3.5.

TABLE A103.3.2
2 X 6: STRAP WALL

	Siding Material/Frame Type			
	Lapped Wood		T1-11	
	STD	ADV	STD	ADV
R-19 + R-11 Batts	0.036	0.035	0.038	0.036
R-19 + R-8 Batts	0.041	0.039	0.042	0.040

TABLE A103.3.3(1)
2 X 6 + 2 X 4: DOUBLE WOOD STUD

Batt Configuration			Siding Material/Frame Type			
			Lapped Wood		T1-11	
Exterior	Middle	Interior	STD	ADV	STD	ADV
R-19	--	R-11	0.040	0.037	0.041	0.038
R-19	--	R-19	0.034	0.031	0.035	0.032
R-19	R-8	R-11	0.029	0.028	0.031	0.029
R-19	R-11	R-11	0.027	0.026	0.028	0.027
R-19	R-11	R-19	0.024	0.023	0.025	0.023
R-19	R-19	R-19	0.021	0.020	0.021	0.020

TABLE A103.3.3(2)
2 X 4 + 2 X 4: DOUBLE WOOD STUD

Batt Configuration			Siding Material/Frame Type			
			Lapped Wood		T1-11	
Exterior	Middle	Interior	STD	ADV	STD	ADV
R-11	--	R-11	0.050	0.046	0.052	0.048
R-19	--	R-11	0.039	0.037	0.043	0.039
R-11	R-8	R-11	0.037	0.035	0.036	0.036
R-11	R-11	R-11	0.032	0.031	0.033	0.032
R-13	R-13	R-13	0.029	0.028	0.029	0.028
R-11	R-19	R-11	0.026	0.026	0.027	0.026

TABLE A103.3.4
LOG WALLS

Average Log Diameter, Inches	U-factor
6	0.148
8	0.111
10	0.089
12	0.074
14	0.063
16	0.056

NOTE:
R-value of wood: R-1.25 per inch thickness

Average wall thickness 90% average log diameter

TABLE A103.3.5
STRESS SKIN PANEL

Panel Thickness, Inches	U-factor
3 1/2	0.071
5 1/2	0.048
7 1/4	0.037
9 1/4	0.030
11 1/4	0.025

NOTE:
R-value of expanded polystyrene: R-3.85 per inch

Framing: 6%

Spline: 8%

No thermal bridging between interior and exterior splines

A103.3.6 Metal stud walls. The nominal R-values in Tables A103.3.6.1 through A103.3.6.3 may be used for purposes of calculating metal stud wall section U-factors in lieu of the ASHRAE zone calculation method as provided in Chapter 27 of the ASHRAE Fundamentals Handbook.

A103.3.6.1 Metal stud wall, overall assembly U-factors. Tables A103.3.6.1(1) and A103.6.1(2): Assumes metal studs spaced on 16 or 24 inch centers with insulation installed to fill wall cavities. Continuous rigid board insulation is applied without creating uninsulated voids in the wall assembly.

A103.3.6.2 Metal stud wall, effective R-values for metal framing and cavity only. Table A103.3.6.2: These values may be used for the metal-framing/cavity layers in walls with metal studs spaced on 16- or 24-inch centers with insulation installed to fill wall cavities in lieu of using the zone method provided in Chapter 25 of the ASHRAE Fundamentals Handbook.

A103.3.6.3 Metal building wall. Table A103.3.6.3: A wall whose structure consists of metal spanning panels supported by steel structural members (does not include spandrel glass or metal panels in curtain wall systems). The first nominal R-value is for insulation compressed between metal wall panels and the steel structure. For double-layer installations, the second rated R-value of insulation is for insulation installed from the inside, covering the girts. For continuous insulation (e.g., insulation boards) it is assumed that the insulation boards are installed on the inside of the girts and uninterrupted by the framing members. Insulation exposed to the conditioned space or semi-heated space shall have a facing, and all insulation seams shall be continuously sealed to provide a continuous air barrier.

A103.3.7 Concrete and masonry walls.

A103.3.7.1 Concrete masonry walls. The nominal R-values in Tables A103.3.7.1(1) and A103.3.7.1(2) may be used for purposes of calculating concrete masonry wall section U-factors in lieu of the ASHRAE isothermal planes calculation method as provided in Chapter 27 of the ASHRAE Fundamentals Handbook

A103.3.7.2 Peripheral edges of intermediate concrete floors. See Table A103.3.7.2.

.

TABLE A103.3.6.1(1)
OVERALL ASSEMBLY U-FACTORS
FOR METAL STUD WALLS WITH CONTINUOUS INSULATION

Metal Framing	R-Value of Continuous Foam Board Insulation	Cavity Insulation					
		R-0	R-11	R-13	R-15	R-19	R-21
16" o.c.	R-0 (none)	0.352	0.132	0.124	0.118	0.109	0.106
	R-1	0.260	0.117	0.111	0.106	0.099	0.096
	R-2	0.207	0.105	0.100	0.096	0.090	0.087
	R-3	0.171	0.095	0.091	0.087	0.082	0.080
	R-4	0.146	0.087	0.083	0.080	0.076	0.074
	R-5	0.128	0.080	0.077	0.074	0.071	0.069
	R-6	0.113	0.074	0.071	0.069	0.066	0.065
	R-7	0.102	0.069	0.066	0.065	0.062	0.061
	R-8	0.092	0.064	0.062	0.061	0.058	0.057
	R-9	0.084	0.060	0.059	0.057	0.055	0.054
	R-10	0.078	0.057	0.055	0.054	0.052	0.051
	R-11	0.072	0.054	0.052	0.051	0.050	0.049
	R-12	0.067	0.051	0.050	0.049	0.047	0.047
	R-13	0.063	0.049	0.048	0.047	0.045	0.045
	R-14	0.059	0.046	0.045	0.045	0.043	0.043
	R-15	0.056	0.044	0.043	0.043	0.041	0.041
	R-20	0.044	0.036	0.036	0.035	0.034	0.034
24" o.c	R-0 (none)	0.338	0.116	0.108	0.102	0.094	0.090
	R-1	0.253	0.104	0.098	0.092	0.086	0.083
	R-2	0.202	0.094	0.089	0.084	0.079	0.077
	R-3	0.168	0.086	0.082	0.078	0.073	0.071
	R-4	0.144	0.079	0.075	0.072	0.068	0.066
	R-5	0.126	0.073	0.070	0.067	0.064	0.062
	R-6	0.112	0.068	0.066	0.063	0.060	0.059
	R-7	0.100	0.064	0.062	0.059	0.057	0.055
	R-8	0.091	0.060	0.058	0.056	0.054	0.052
	R-9	0.084	0.057	0.055	0.053	0.051	0.050
	R-10	0.077	0.054	0.052	0.050	0.048	0.048
	R-11	0.072	0.051	0.049	0.048	0.046	0.045
	R-12	0.067	0.048	0.047	0.046	0.044	0.043
	R-13	0.063	0.046	0.045	0.044	0.042	0.042
	R-14	0.059	0.044	0.043	0.042	0.041	0.040
	R-15	0.056	0.042	0.041	0.040	0.039	0.038
	R-20	0.044	0.035	0.034	0.034	0.033	0.032

Continuous foam board insulation: Continuous insulation assumes no thermal bridging of insulation by framing or z-furring through applied foam board. Zone calculation method as provided in the ASHRAE Fundamentals Handbook must be used for thermally bridged foam board insulation. Values for attachment of insulation with z-furring are given in Table A103.3.6.1(2).

TABLE A105.3.6.1(2)
OVERALL ASSEMBLY U-FACTORS FOR METAL STUD WALLS WITH INSULATION SUPPORTED BY Z-FURRING

Metal Framing	R-value of Foam Board Insulation	Z-furring Attachment	Cavity Insulation					
			R-0	R-11	R-13	R-15	R-19	R-21
16" o.c.	R-0 (none)	Horizontal	0.352	0.132	0.124	0.118	0.109	0.106
	R-5	Horizontal	0.155	0.089	0.086	0.083	0.078	0.077
	R-7.5	Horizontal	0.128	0.080	0.077	0.074	0.071	0.069
	R-10	Horizontal	0.110	0.072	0.070	0.068	0.065	0.064
	R-12.5	Horizontal	0.099	0.068	0.065	0.064	0.061	0.060
	R-15	Horizontal	0.091	0.064	0.062	0.060	0.058	0.057
	R-17.5	Horizontal	0.084	0.060	0.058	0.057	0.055	0.054
	R-20	Horizontal	0.078	0.057	0.056	0.054	0.052	0.052
	R-22.5	Horizontal	0.074	0.055	0.054	0.052	0.051	0.050
	R-25	Horizontal	0.071	0.053	0.052	0.051	0.049	0.048
	R-0 (none)	Vertical	0.352	0.132	0.124	0.118	0.109	0.106
	R-5	Vertical	0.165	0.093	0.089	0.086	0.081	0.079
	R-7.5	Vertical	0.142	0.085	0.081	0.079	0.075	0.073
	R-10	Vertical	0.126	0.079	0.076	0.074	0.070	0.069
	R-12.5	Vertical	0.115	0.074	0.072	0.070	0.066	0.065
	R-15	Vertical	0.107	0.071	0.069	0.067	0.064	0.063
	R-17.5	Vertical	0.100	0.068	0.065	0.064	0.061	0.060
	R-20	Vertical	0.094	0.065	0.063	0.061	0.059	0.058
	R-22.5	Vertical	0.090	0.063	0.061	0.060	0.057	0.056
	R-25	Vertical	0.086	0.061	0.059	0.058	0.056	0.055
24" o.c.	R-0 (none)	Horizontal	0.338	0.116	0.108	0.102	0.094	0.09
	R-5	Horizontal	0.152	0.082	0.078	0.074	0.070	0.068
	R-7.5	Horizontal	0.126	0.074	0.070	0.068	0.064	0.062
	R-10	Horizontal	0.109	0.067	0.065	0.062	0.059	0.058
	R-12.5	Horizontal	0.098	0.063	0.061	0.059	0.056	0.055
	R-15	Horizontal	0.090	0.060	0.058	0.056	0.053	0.052
	R-17.5	Horizontal	0.083	0.057	0.055	0.053	0.051	0.050
	R-20	Horizontal	0.078	0.054	0.052	0.051	0.049	0.048
	R-22.5	Horizontal	0.074	0.052	0.050	0.049	0.047	0.046
	R-25	Horizontal	0.070	0.050	0.049	0.047	0.046	0.045
	R-0 (none)	Vertical	0.338	0.116	0.108	0.102	0.094	0.09
	R-5	Vertical	0.162	0.084	0.080	0.077	0.072	0.070
	R-7.5	Vertical	0.140	0.078	0.074	0.071	0.067	0.065
	R-10	Vertical	0.124	0.073	0.070	0.067	0.063	0.062
	R-12.5	Vertical	0.113	0.069	0.066	0.064	0.061	0.059
	R-15	Vertical	0.106	0.066	0.063	0.061	0.058	0.057
	R-17.5	Vertical	0.098	0.063	0.061	0.059	0.056	0.055
	R-20	Vertical	0.093	0.061	0.059	0.057	0.054	0.053
	R-22.5	Vertical	0.089	0.059	0.057	0.055	0.053	0.051
	R-25	Vertical	0.085	0.057	0.055	0.054	0.051	0.050

Values may in Table A105.3.6.1(2) may not interpolated between. The value of the foam board insulation must meet exceed the value listed in the table in order to use the value shown.

TABLE A103.3.6.2
EFFECTIVE R-VALUES FOR METAL FRAMING AND CAVITY ONLY

	Cavity		Insulation		
	Nominal Depth, Inches	Actual Depth, Inches	Nominal R-Value	Effective R-Value	
				16" O.C.	24" O.C.
Air Cavity	Any	Any	R-0.91 (air)	0.79	0.91
Wall	4	3-1/2	R-11	5.5	6.6
	4	3-1/2	R-13	6.0	7.2
	4	3-1/2	R-15	6.4	7.8
	6	5-1/2	R-19	7.1	8.6
	6	5-1/2	R-21	7.4	9.0
	8	7-1/4	R-25	7.8	9.6
Roof		Insulation is uncompressed	R-11	5.5	6.1
			R-19	7.0	9.1
			R-30	9.3	11.4

TABLE A103.3.6.3
DEFAULT METAL BUILDING WALL U-FACTORS

Insulation System	Rated R-Value of Insulation	Overall U-fFactor for Entire Base Wall Assembly	Overall U-Factor for Assembly of Base Wall Plus Continuous Insulation (Uninterrupted by Framing)					
			R-6.5	R-13	R-19.5	R-26	R-32.5	R-39
Single Layer of Mineral Fiber								
	None	1.180	0.136	0.072	0.049	0.037	0.030	0.025
	R-10	0.186	0.084	0.054	0.040	0.032	0.026	0.023
	R-11	0.185	0.084	0.054	0.040	0.032	0.026	0.023
	R-13	0.162	0.079	0.052	0.039	0.031	0.026	0.022
	R-16	0.155	0.077	0.051	0.039	0.031	0.026	0.022
	R-19	0.147	0.075	0.050	0.038	0.030	0.025	0.022

TABLE A103.3.7.1(1)
DEFAULT U-FACTORS FOR CONCRETE AND MASONRY WALLS

8" Concrete Masonry

WALL DESCRIPTION	CORE TREATMENT			
	Partial Grout with Ungrouted Cores			Solid Grout
	Empty	Loose-fill insulated		
		Perlite	Vermiculite	
Exposed Block, Both Sides	0.40	0.23	0.24	0.43
R-5 Interior Insulation, Wood Furring	0.14	0.11	0.12	0.15
R-6 Interior Insulation, Wood Furring	0.14	0.11	0.11	0.14
R-10.5 Interior Insulation, Wood Furring	0.11	0.09	0.09	0.11
R-8 Interior Insulation, Metal Clips	0.11	0.09	0.09	0.11
R-6 Exterior Insulation	0.12	0.10	0.10	0.12
R-10 Exterior Insulation	0.08	0.07	0.07	0.08
R-9.5 Rigid Polystyrene Integral Insulation, Two Webbed Block	0.11	0.09	0.09	0.12

TABLE A103.3.7.1(1) – continued
DEFAULT U-FACTORS FOR CONCRETE AND MASONRY WALLS

12" Concrete Masonry

WALL DESCRIPTION	CORE TREATMENT			
	Partial Grout with Ungrouted Cores			Solid Grout
	Empty	Loose-fill insulated		
		Perlite	Vermiculite	
Exposed Block, Both Sides	0.35	0.17	0.18	0.33
R-5 Interior Insulation, Wood Furring	0.14	0.10	0.10	0.13
R-6 Interior Insulation, Wood Furring	0.13	0.09	0.10	0.13
R-10.5 Interior Insulation, Wood Furring	0.11	0.08	0.08	0.10
R-8 Interior Insulation, Metal Clips	0.10	0.08	0.08	0.09
R-6 Exterior Insulation	0.11	0.09	0.09	0.11
R-10 Exterior Insulation	0.08	0.06	0.06	0.08
R-9.5 Rigid Polystyrene Integral Insulation, Two Webbed Block	0.11	0.08	0.09	0.12

8" Clay Brick

WALL DESCRIPTION	CORE TREATMENT			
	Partial Grout with Ungrouted Cores			Solid Grout
	Empty	Loose-fill insulated		
		Perlite	Vermiculite	
Exposed Block, Both Sides	0.50	0.31	0.32	0.56
R-5 Interior Insulation, Wood Furring	0.15	0.13	0.13	0.16
R-6 Interior Insulation, Wood Furring	0.15	0.12	0.12	0.15
R-10.5 Interior Insulation, Wood Furring	0.12	0.10	0.10	0.12
R-8 Interior Insulation, Metal Clips	0.11	0.10	0.10	0.11
R-6 Exterior Insulation	0.12	0.11	0.11	0.13
R-10 Exterior Insulation	0.08	0.08	0.08	0.09

6" Concrete Poured or Precast

WALL DESCRIPTION	CORE TREATMENT			
	Partial Grout with Ungrouted Cores			Solid Grout
	Empty	Loose-fill insulated		
		Perlite	Vermiculite	
Exposed Concrete, Both Sides	NA	NA	NA	0.61
R-5 Interior Insulation, Wood Furring	NA	NA	NA	0.16
R-6 Interior Insulation, Wood Furring	NA	NA	NA	0.15
R-10.5 Interior Insulation, Wood Furring	NA	NA	NA	0.12
R-8 Interior Insulation, Metal Clips	NA	NA	NA	0.12
R-6 Exterior Insulation	NA	NA	NA	0.13
R-10 Exterior Insulation	NA	NA	NA	0.09

1. Grouted cores at 40" x 48" on center vertically and horizontally in partial grouted walls.
2. Interior insulation values include 1/2" gypsum board on the inner surface.
3. Furring and stud spacing is 16" on center. Insulation is assumed to fill furring space and is not compressed.
4. Intermediate values may be interpolated using this table. Values not contained in this table may be computed using the procedures listed in the ASHRAE Fundamentals Handbook.
5. Concrete Masonry Unit (CMU) assembly U-values are based on local test data for Washington state CMU block material using the ASTM C-236-87 steady state thermal conductance test. Tests included an 8"x8"x16" CMU with all cells filled with vermiculite (1995) and 8"x8"x16" CMU with all cells filled with polymaster foam in place insulation (1996). Refer to ASHRAE Standard 90.1 for additional nationally recognized data on the thermal performance of CMU block walls.

TABLE A103.3.7.1(2)
DEFAULT U-FACTORS FOR CONCRETE AND MASONRY WALLS

Framing Type and Depth	Rated R-Value of Insulation Alone	Assembly U-Factors for Solid Concrete Walls	Assembly U-Factors for Concrete Block Walls: Solid Grouted	Assembly U-Factors for Concrete Block Walls: Partially Grouted (cores uninsulated except where specified)
Base Wall only				
No Framing	R-0	U-0.740	U-0.580	U-0.480
	Ungrouted Cores Filled with Loose-Fill Insulation	N.A.	N.A.	U-0.350
Continuous Wood Framing				
0.75 in.	R-3.0	U-0.247	U-0.226	U-0.210
1.5 in.	R-6.0	U-0.160	U-0.151	U-0.143
2.0 in.	R-10.0	U-0.116	U-0.111	U-0.107
3.5 in.	R-11.0	U-0.094	U-0.091	U-0.088
3.5 in.	R-13.0	U-0.085	U-0.083	U-0.080
3.5 in.	R-15.0	U-0.079	U-0.077	U-0.075
5.5 in.	R-19.0	U-0.060	U-0.059	U-0.058
5.5 in.	R-21.0	U-0.057	U-0.055	U-0.054
Continuous Metal Framing at 24 in. on center horizontally				
1.0 in.	R-0.0	U-0.414	U-0.359	U-0.318
1.0 in.	R-3.8	U-0.325	U-0.290	U-0.263
1.0 in.	R-5.0	U-0.314	U-0.281	U-0.255
1.0 in.	R-6.5	U-0.305	U-0.274	U-0.249
1.5 in.	R-11.0	U-0.267	U-0.243	U-0.223
2.0 in.	R-7.6	U-0.230	U-0.212	U-0.197
2.0 in.	R-10.0	U-0.219	U-0.202	U-0.188
2.0 in.	R-13.0	U-0.210	U-0.195	U-0.182
3.0 in.	R-11.4	U-0.178	U-0.167	U-0.157
3.0 in.	R-15.0	U-0.168	U-0.158	U-0.149
3.0 in.	R-19.0	U-0.161	U-0.152	U-0.144
3.5 in.	R-11.0	U-0.168	U-0.158	U-0.149
3.5 in.	R-13.0	U-0.161	U-0.152	U-0.144
3.5 in.	R-15.0	U-0.155	U-0.147	U-0.140
4.5 in.	R-17.1	U-0.133	U-0.126	U-0.121
4.5 in.	R-22.5	U-0.124	U-0.119	U-0.114
4.5 in.	R-25.2	U-0.122	U-0.116	U-0.112
5.0 in.	R-19.0	U-0.122	U-0.117	U-0.112
5.0 in.	R-25.0	U-0.115	U-0.110	U-0.106
5.0 in.	R-28.0	U-0.112	U-0.107	U-0.103
5.0 in.	R-32.0	U-0.109	U-0.105	U-0.101
5.5 in.	R-19.0	U-0.118	U-0.113	U-0.109
5.5 in.	R-20.9	U-0.114	U-0.109	U-0.105
5.5 in.	R-21.0	U-0.113	U-0.109	U-0.105
5.5 in.	R-27.5	U-0.106	U-0.102	U-0.099
5.5 in.	R-30.8	U-0.104	U-0.100	U-0.096

TABLE A103.3.7.1(2) – continued
DEFAULT U-FACTORS FOR CONCRETE AND MASONRY WALLS

Framing Type and Depth	Rated R-Value of Insulation Alone	Assembly U-Factors for Solid Concrete Walls	Assembly U-Factors for Concrete Block Walls: Solid Grouted	Assembly U-Factors for Concrete Block Walls: Partially Grouted (cores uninsulated except where specified)
6.0 in.	R-22.8	U-0.106	U-0.102	U-0.098
6.0 in.	R-30.0	U-0.099	U-0.095	U-0.092
6.0 in.	R-33.6	U-0.096	U-0.093	U-0.090
6.5 in.	R-24.7	U-0.099	U-0.096	U-0.092
7.0 in.	R-26.6	U-0.093	U-0.090	U-0.087
7.5 in.	R-28.5	U-0.088	U-0.085	U-0.083
8.0 in.	R-30.4	U-0.083	U-0.081	U-0.079
1 in Metal Clips at 24 in. on center horizontally and 16 in. vertically (also, where allowed by Section 1332, for assemblies with a ratio of metal penetration area/ mass wall area of <0.0004 or <0.04% of the mass wall area)[5]				
1.0 in.	R-3.8	U-0.210	U-0.195	U-0.182
1.0 in.	R-5.0	U-0.184	U-0.172	U-0.162
1.0 in.	R-5.6	U-0.174	U-0.163	U-0.154
1.5 in.	R-5.7	U-0.160	U-0.151	U-0.143
1.5 in.	R-7.5	U-0.138	U-0.131	U-0.125
1.5 in.	R-8.4	U-0.129	U-0.123	U-0.118
2.0 in.	R-7.6	U-0.129	U-0.123	U-0.118
2.0 in.	R-10.0	U-0.110	U-0.106	U-0.102
2.0 in.	R-11.2	U-0.103	U-0.099	U-0.096
2.5 in.	R-9.5	U-0.109	U-0.104	U-0.101
2.5 in.	R-12.5	U-0.092	U-0.089	U-0.086
2.5 in.	R-14.0	U-0.086	U-0.083	U-0.080
3.0 in.	R-11.4	U-0.094	U-0.090	U-0.088
3.0 in.	R-15.0	U-0.078	U-0.076	U-0.074
3.0 in.	R-16.8	U-0.073	U-0.071	U-0.069
3.5 in.	R-13.3	U-0.082	U-0.080	U-0.077
3.5 in.	R-17.5	U-0.069	U-0.067	U-0.065
3.5 in.	R-19.6	U-0.064	U-0.062	U-0.061
4.0 in.	R-15.2	U-0.073	U-0.071	U-0.070
4.0 in.	R-20.0	U-0.061	U-0.060	U-0.058
4.0 in.	R-22.4	U-0.057	U-0.056	U-0.054
5.0 in.	R-28.0	U-0.046	U-0.046	U-0.045
6.0 in.	R-33.6	U-0.039	U-0.039	U-0.038
7.0 in.	R-39.2	U-0.034	U-0.034	U-0.033
8.0 in.	R-44.8	U-0.030	U-0.030	U-0.029
9.0 in.	R-50.4	U-0.027	U-0.027	U-0.026
10.0 in.	R-56.0	U-0.024	U-0.024	U-0.024
11.0 in.	R-61.6	U-0.022	U-0.022	U-0.022

TABLE A103.3.7.1(2) – continued
DEFAULT U-FACTORS FOR CONCRETE AND MASONRY WALLS

Framing Type and Depth	Rated R-Value of Insulation Alone	Assembly U-Factors for Solid Concrete Walls	Assembly U-Factors for Concrete Block Walls: Solid Grouted	Assembly U-Factors for Concrete Block Walls: Partially Grouted (cores uninsulated except where specified)
Continuous Insulation Uninterrupted by Framing				
No Framing	R-1.0	U-0.425	U-0.367	U-0.324
	R-2.0	U-0.298	U-0.269	U-0.245
	R-3.0	U-0.230	U-0.212	U-0.197
	R-4.0	U-0.187	U-0.175	U-0.164
	R-5.0	U-0.157	U-0.149	U-0.141
No Framing	R-6.0	U-0.136	U-0.129	U-0.124
	R-7.0	U-0.120	U-0.115	U-0.110
	R-8.0	U-0.107	U-0.103	U-0.099
	R-9.0	U-0.097	U-0.093	U-0.090
	R-10.0	U-0.088	U-0.085	U-0.083
No Framing	R-11.0	U-0.081	U-0.079	U-0.076
	R-12.0	U-0.075	U-0.073	U-0.071
	R-13.0	U-0.070	U-0.068	U-0.066
	R-14.0	U-0.065	U-0.064	U-0.062
	R-15.0	U-0.061	U-0.060	U-0.059
No Framing	R-16.0	U-0.058	U-0.056	U-0.055
	R-17.0	U-0.054	U-0.053	U-0.052
	R-18.0	U-0.052	U-0.051	U-0.050
	R-19.0	U-0.049	U-0.048	U-0.047
	R-20.0	U-0.047	U-0.046	U-0.045
No Framing	R-21.0	U-0.045	U-0.044	U-0.043
	R-22.0	U-0.043	U-0.042	U-0.042
	R-3.0	U-0.041	U-0.040	U-0.040
	R-24.0	U-0.039	U-0.039	U-0.038
	R-25.0	U-0.038	U-0.037	U-0.037
No Framing	R-30.0	U-0.032	U-0.032	U-0.031
	R-35.0	U-0.028	U-0.027	U-0.027
	R-40.0	U-0.024	U-0.024	U-0.024
	R-45.0	U-0.022	U-0.021	U-0.021
	R-50.0	U-0.019	U-0.019	U-0.019
	R-55.0	U-0.018	U-0.018	U-0.018
	R-60.0	U-0.016	U-0.016	U-0.016
Brick cavity wall with continuous insulation				
No Framing	R-0.0	U-0.337	U-0.299	U-0.270
No Framing	R-3.8	U-0.148	U-0.140	U-0.133
No Framing	R-5.0	U-0.125	U-0.120	U-0.115
No Framing	R-6.5	U-0.106	U-0.102	U-0.098
No Framing	R-7.6	U-0.095	U-0.091	U-0.088
No Framing	R-10.0	U-0.077	U-0.075	U-0.073
No Framing	R-10.5	U-0.079	U-0.077	U-0.075
No Framing	R-11.4	U-0.070	U-0.068	U-0.066

TABLE A103.3.7.1(2) – continued
DEFAULT U-FACTORS FOR CONCRETE AND MASONRY WALLS

Framing Type and Depth	Rated R-Value of Insulation Alone	Assembly U-Factors for Solid Concrete Walls	Assembly U-Factors for Concrete Block Walls: Solid Grouted	Assembly U-Factors for Concrete Block Walls: Partially Grouted (cores uninsulated except where specified)
No Framing	R-15.0	U-0.056	U-0.055	U-0.053
No Framing	R-16.5	U-0.054	U-0.053	U-0.052
No Framing	R-19.0	U-0.046	U-0.045	U-0.044
No Framing	R-22.5	U-0.041	U-0.040	U-0.039
No Framing	R-28.5	U-0.033	U-0.032	U-0.032
Continuous Insulation Uninterrupted by Framing with Stucco and Continuous Metal Framing at 24 in. on center horizontally				
1.0 in.	R-0.0 + R-19 c.i.	U-0.047	U-0.046	U-0.045
1.0 in.	R-3.8 + R-19 c.i.	U-0.045	U-0.044	U-0.044
1.0 in.	R-5.0 + R-19 c.i.	U-0.045	U-0.044	U-0.043
1.0 in.	R-6.5 + R-19 c.i.	U-0.045	U-0.044	U-0.043
1.5 in.	R-11.0 + R-19 c.i.	U-0.044	U-0.043	U-0.043
2.0 in.	R-7.6 + R-19 c.i.	U-0.043	U-0.042	U-0.041
2.0 in.	R-10.0 + R-19 c.i.	U-0.042	U-0.041	U-0.041
2.0 in.	R-13.0 + R-19 c.i.	U-0.042	U-0.041	U-0.041
3.0 in.	R-11.4 + R-19 c.i.	U-0.041	U-0.040	U-0.039
3.0 in.	R-15.0 + R-19 c.i.	U-0.040	U-0.039	U-0.039
3.0 in.	R-19.0 + R-19 c.i.	U-0.040	U-0.039	U-0.038
3.5 in.	R-11.0 + R-19 c.i.	U-0.040	U-0.039	U-0.039
3.5 in.	R-13.0 + R-19 c.i.	U-0.040	U-0.039	U-0.038
5.0 in.	R-19.0 + R-19 c.i.	U-0.037	U-0.036	U-0.036
5.0 in.	R-25.0 + R-19 c.i.	U-0.036	U-0.035	U-0.035
5.0 in.	R-32.5 + R-19 c.i.	U-0.035	U-0.035	U-0.034
5.5 in.	R-19.0 + R-19 c.i.	U-0.036	U-0.036	U-0.035
5.5 in.	R-21.0 + R-19 c.i.	U-0.035	U-0.035	U-0.035

Notes for Default Table A103.3.7.1(2):

a. It is acceptable to use the U-factors in Table A103.3.7.1(2) for all concrete and masonry walls, provided that the grouting is equal to or less than that specified.
- -For ungrouted walls, use the partially grouted column.
- -For metal studs and z-furring, use the continuous-metal-framing category.
- -For discontinuous metal clips 1 inch square or smaller, use the metal-clip category.
- -For insulation that is attached without any framing members (e.g. glued), use the continuous-insulation uninterrupted-by-framing category. Continuous insulation may be installed on the interior or exterior of masonry walls, or between stand-alone walls in multilayer masonry walls, or on the interior or exterior of the concrete.

b. For Table A103.3.7.1(2), the U-factor includes R-0.17 for exterior air film and R-0.68 for interior air film-vertical surfaces. For insulated walls, the U-factor also includes R-0.45 for 0.5 in. gypsum board. U-factors are provided for the following configurations:
1. Concrete wall: 8-in. normal weight concrete wall with a density of 145 lb/ft^3.
2. Solid grouted concrete block wall: 8-in. medium weight ASTM C90 concrete block with a density of 115 lb/ft^3 and solid grouted cores.
3. Partially grouted concrete block wall: 8-in. medium weight ASTM C90 concrete block with a density of 115 lb/ft^3 having reinforcing steel every 32 in. vertically and every 48 in. horizontally, with cores grouted in those areas only. Other cores are filled with insulating material only if there is no other insulation.

c. For walls with insulation contained in a framing layer, the U-factors in Table A103.3.7.1(2) assume contact (and thermal bridging) between the mass wall and other framing. For wall assemblies with multiple layers where the wood or metal framing layer does not contact the concrete or masonry layer (i.e., walls with an airspace between the stud wall layer and the mass wall layer), it is acceptable to use the appropriate wood or metal frame wall default U-factors in Tables A103.3.1 or A103.3.6.1. Note: It is acceptable to use this approach where the insulation extends beyond the framing and is in contact with the mass wall layer (e.g. a nominal four-inch metal stud containing insulation that is nominally six inches thick and therefore extends two inches beyond the back of the metal stud).

d. Except for wall assemblies qualifying for note 3, if not taken from Table A103.3.7.1(2), mass wall U-factors shall be determined in accordance with ASHRAE 90.1, Appendix A, Section A3.1 and Tables A3.1A to A3.1D, or Section A9.4.

TABLE A103.3.7.2
DEFAULT U-FACTORS FOR PERIPHERAL EDGES OF INTERMEDIATE CONCRETE FLOORS

Slab Edge Treatment	Average Thickness of Wall Above and Below			
	6 inches	8 inches	10 inches	12 inches
Exposed Concrete	0.816	0.741	0.678	0.625
R-5 Exterior Insulation	0.161	0.157	0.154	0.152
R-6 Exterior Insulation	0.138	0.136	0.134	0.132
R-7 Exterior Insulation	0.122	0.120	0.118	0.116
R-8 Exterior Insulation	0.108	0.107	0.106	0.104
R-9 Exterior Insulation	0.098	0.097	0.095	0.094
R-10 Exterior Insulation	0.089	0.088	0.087	0.086
R-11 Exterior Insulation	0.082	0.081	0.080	0.079
R-12 Exterior Insulation	0.076	0.075	0.074	0.074
R-13 Exterior Insulation	0.070	0.070	0.069	0.068
R-14 Exterior Insulation	0.066	0.065	0.065	0.064
R-15 Exterior Insulation	0.062	0.061	0.061	0.060

Notes for Table A103.3.7.2:

a. Exterior insulation values listed above are continuous R-values on the exterior side of the concrete floor.

b. For conditions with an exterior wall above the peripheral edge of intermediate concrete floor but with no wall below the intermediate concrete floor this table may be used as long as the code minimum insulation is applied to the floor slab below the concrete floor.

c. Typical conditions where conditioned space building envelope wall thermal insulation values are broken concrete floors include, but are not limited to, the following examples:
   1. Elevator hoistway shafts that serve the conditioned building and pass through unconditioned floors such as parking garage levels;
   2. Stairwell enclosures that serve the conditioned building and pass through unconditioned floors such as parking garage levels;
   3. Walls between interior and exterior building envelope that separate the interior conditioned space from an exterior courtyard or roofdeck;
   4. Walls between interior and exterior building envelope that separate the interior conditioned space from an exterior unconditioned space on parking garage levels.

SECTION A104
BELOW-GRADE WALLS AND SLABS

A104.1 General. Table A104.1 lists heat loss coefficients for below-grade walls and floors.

Coefficients for below-grade walls are given as U-factors (Btu/h × ft^2 × °F of wall area). Coefficients for below-grade slabs are listed as F-factors (Btu/h × ft × °F per lineal foot of slab perimeter).

Below-grade wall U-factors are only valid when used with the accompanying below-grade slab F-factor, and vice versa.

A104.2 Component description. All below-grade walls are assumed to be 8 inch concrete. The wall is assumed to extend from the slab upward to the top of the mud sill for the distance specified in Table A104.1, with 6 inches of concrete wall extending above grade.

Interior insulation is assumed to be fiberglass batts placed in the cavity formed by 2 x 4 framing on 24 inch centers with 1/2 inch gypsum board as the interior finish material. Exterior insulation is assumed to be applied directly to the exterior of the below-grade wall from the top of the wall to the footing. The exterior case does not assume any interior framing or sheetrock.

In all cases, the entire wall surface is assumed to be insulated to the indicated nominal level with the appropriate framing and insulation application. Coefficients are listed for wall depths of 2, 3-1/2 and 7 feet below grade. Basements shallower than two feet should use on-grade slab coefficients.

Heat-loss calculations for wall areas above-grade should use above-grade wall U-factors, beginning at the mudsill.

TABLE A104.1
DEFAULT WALL U-FACTORS AND SLAB F-FACTORS FOR BASEMENTS

	Below Grade Wall U-factor	Below Grade Slab F-factor
2 Foot Depth Below Grade		
Uninsulated	0.350	0.59
R-11 Interior	0.066	0.68
R-11 Interior w/TB	0.070	0.60
R-19 Interior	0.043	0.69
R-19 Interior w/TB	0.045	0.61
R-10 Exterior	0.070	0.60
R-12 Exterior	0.061	0.60
3.5 Foot Depth Below Grade		
Uninsulated	0.278	0.53
R-11 Interior	0.062	0.63
R-11 Interior w/TB	0.064	0.57
R-19 Interior	0.041	0.64
R-19 Interior w/TB	0.042	0.57
R-10 Exterior	0.064	0.57
R-12 Exterior	0.057	0.57
7 Foot Depth Below Grade		
Uninsulated	0.193	0.46
R-11 Interior	0.054	0.56
R-11 Interior w/TB	0.056	0.42
R-19 Interior	0.037	0.57
R-19 Interior w/TB	0.038	0.43
R-10 Exterior	0.056	0.42
R-12 Exterior	0.050	0.42

TB = Thermal Break

A104.3 Insulation description. Coefficients are listed for the following four configurations:

1. **Uninsulated:** No insulation or interior finish.
2. **Interior insulation:** Interior 2 x 4 insulated wall without a thermal break between concrete wall and slab.
3. **Interior insulation with thermal break:** Interior 2 x 4 insulated wall with R-5 rigid board providing a thermal break between the concrete wall and the slab.
4. **Exterior insulation:** Insulation applied directly to the exterior surface of the concrete wall.

SECTION A105
FLOORS OVER UNCONDITIONED SPACE

A105.1 General. Tables A105.1(1), A105.1(2) and A105.1(3) list heat loss coefficients for floors over unconditioned spaces in units of Btu/h × ft^2 × °F.

They are derived from procedures listed in the ASHRAE Fundamentals Handbook, assuming an average outdoor temperature of 45°F, an average indoor temperature of 65°F and a crawlspace area of 1350 ft^2 and 100 feet of perimeter. The crawlspace is assumed to be 2.5 feet high, with 24 inches below grade and 6 inches above grade.

TABLE A105.1(1)
DEFAULT U-FACTORS FOR FLOORS OVER VENTED CRAWLSPACE OR UNHEATED BASEMENT

Nominal R-Value		U-Factor	
Floor	Perimeter	Post & Beam	Joists
0	0	0.112	0.134
	11	0.100	0.116
	19	0.098	0.114
	30	0.093	0.107
11	0	0.052	0.056
	11	0.048	0.052
19	0	0.038	0.041
	11	0.036	0.038
22	0	0.034	0.037
	11	0.033	0.035
25	0	0.032	0.034
	11	0.031	0.033
30	0	0.028	0.029
	11	0.027	0.028
38	0	0.024	0.025
	11	0.024	0.024

TABLE A105.1(2)
DEFAULT U-FACTORS FOR FLOORS OVER HEATED PLENUM CRAWLSPACES

Nominal R-Value Perimeter	U-Factor
11	0.085
19	0.075
30	0.069

Note: Crawlspaces used as heated plenums have approximately 30% higher heat loss rate than unvented crawlspaces with the same assumed ACH. Default U-factors in Table A105.1(2) reflect this higher rate of heat loss.

TABLE A105.1(3)
DEFAULT U-FACTORS FOR EXPOSED FLOORS

U-Factor			
Nominal R-Value	Concrete	Wood Joist	Metal Joist
R-11	0.077	0.088	0.14
R-15	0.059	0.076	0.12
R-19	0.048	0.062	0.11
R-21	0.043	0.057	0.11
R-25	0.037	0.051	0.10
R-30	0.031	0.040	0.09
R-38	0.025	0.034	0.08

A105.2 Crawlspace description. Four configurations are considered: Naturally ventilated crawlspace, mechanically vented crawlspace, heated plenum crawlspace and exposed floor.

A105.2.1 Naturally ventilated crawlspaces. Assumed to have 3.0 air changes per hour, with at least 1.0 ft^2 of net-free ventilation in the foundation for every 300 ft^2 of crawlspace floor area. The crawlspace is not actively heated. Floors over unheated areas, such as garages, may only use those values which have R-0 perimeter insulation.

A105.2.2 Mechanically ventilated crawlspaces. Assume to have 1.5 air changes per hour, with less than 1.0 ft^2 of net-free ventilation in the foundation for every 300 ft^2 of crawlspace floor area. The crawlspace is not actively heated. Floors over unheated basements may only use those values which have R-0 perimeter insulation.

A105.2.3 Heated plenum crawlspaces. Assumed to have 0.25 air changes per hour, with no foundation vents. Heated supply air from central furnace is blown into a crawlspace and allowed to enter the living space unducted via holes cut into the floor.

A105.2.4 Exposed floors. Assumes no buffer space, and a covering of 1/2 inch T1-11 on the exterior of the cavity exposed to the outside air or rigid insulation below a concrete floor, such as over parking garages.

A105.3 Construction description. Floors are assumed to be either joisted floors framed on 16 inch centers, or post and beam on 4 foot by 8 foot squares. Insulation is assumed to be installed under the subflooring between the joists or beams with no space between the insulation and the subfloor. Insulation is assumed to be uncompressed. Exposed floors also include concrete with continuous rigid insulation assumed.

Perimeter insulation is assumed to extend from the top of the rim joist to the crawlspace floor and then inward along the ground (on top of the ground cover) for at least 24 inches.

Floor coverings are assumed to be light carpet with rubber pad.

SECTION A106
ON-GRADE SLAB FLOORS

A106.1 General. Table A106.1 lists heat loss coefficients for heated on-grade slab floors, in units of Btu/h × °F per lineal foot of perimeter.

TABLE A106.1
DEFAULT F-FACTORS FOR ON-GRADE SLABS

Insulation type	R-0	R-5	R-10	R-15
Unheated Slab				
Uninsulated slab	0.73	--	--	--
2 ft Horizontal (No thermal break)	--	0.70	0.70	0.69
4 ft Horizontal (No thermal break)	--	0.67	0.64	0.63
2 ft Vertical	--	0.58	0.54	0.52
4 ft Vertical	--	0.54	0.48	0.45
Fully insulated slab	--	--	0.36	--
Heated Slab				
Uninsulated slab	0.84	--	--	--
Fully insulated slab	--	0.74	0.55	0.44
R-5 Center (With perimeter insulation)	--	--	0.66	0.62
R-10 Center (With perimeter insulation)	--	--	--	0.51
3 ft Vertical	--	--	0.78	--

A106.2 Component description. All on-grade slab floors are assumed to be 6 inch concrete poured directly onto the earth. The bottom of the slab is assumed to be at grade line. Monolithic and floating slabs are not differentiated.

Soil is assumed to have a conductivity of 0.75 Btu/h × ft^2 × °F. Slabs 2 feet or more below grade should use basement coefficients.

A106.3 Insulation description. Coefficients are provided for the following three configurations:

1. **Two foot (or four foot) vertical:** Insulation is applied directly to the slab exterior, extending downward from the top of the slab to a depth of 2 feet (or 4 feet) below grade.
2. **Two foot (or four foot) horizontal:** Insulation is applied directly to the underside of the slab, and run horizontally from the perimeter inward for 2 feet (or 4 feet). The slab edge is exposed in this configuration.

   Note: A horizontal installation with a thermal break of at least R-5 at the slab edge should use the vertical-case F-factors.

3. **Fully insulated slab:** Insulation extends from the top of the slab, along the entire perimeter, and completely covers the area under the slab. Thicker perimeter insulation covers the slab edge and extends 2 feet under the slab.

SECTION A107
DEFAULT U-FACTORS FOR DOORS

A107.1 Doors without NFRC certification. Doors that do not have NFRC certification shall be assigned the appropriate U-factor from Tables A107.1(1) through A107.1(4).

TABLE A107.1(1)
DEFAULT U-FACTORS FOR DOORS

Door Type	No Glazed Fenestration	Single Glazing	Double Glazing with ¼ in. Airspace	Double Glazing with ½ in. Airspace	Double Glazing with e=0.10, ½ in. Argon
SWINGING DOORS (Rough opening – 38 in. x 82 in.)					
Slab Doors					
Wood slab in wood frame[a]	0.46				
6% glazed fenestration (22 in. x 8 in. lite)	–	0.48	0.47	0.46	0.44
25% glazed fenestration (22 in.x36 in. lite)	–	0.58	0.48	0.46	0.42
45% glazed fenestration (22 in.x64 in. lite)	–	0.69	0.49	0.46	0.39
More than 50% glazed fenestration	Use Table C303.1.3(1)/R303.1.3(1) as appropriate				
Insulated steel slab with wood edge in wood frame[a]	0.16				
6% glazed fenestration (22 in. x 8 in. lite)	–	0.21	0.20	0.19	0.18
25% glazed fenestration (22 in.x36 in. lite)	–	0.39	0.28	0.26	0.23
45% glazed fenestration (22 in.x64 in. lite)	–	0.58	0.38	0.35	0.26
More than 50% g glazed fenestration	Use Table C303.1.3(1)/R303.1.3(1) as appropriate				
Foam insulated steel slab with metal edge in steel frame[b]	0.37				
6% glazed fenestration (22 in. x 8 in. lite)	–	0.44	0.42	0.41	0.39
25% glazed fenestration (22 in.x36 in. lite)	–	0.55	0.50	0.48	0.44
45% glazed fenestration (22 in.x64 in. lite)	–	0.71	0.59	0.56	0.48
More than 50% glazed fenestration	Use Table C303.1.3(1)/R303.1.3(1) as appropriate				
Cardboard honeycomb slab with metal edge in steel frame[b]	0.61				
Style and Rail Doors					
Sliding glass doors/French doors	Use Table C303.1.3(1)/R303.1.3(1) as appropriate				
Site-Assembled Style and Rail Doors					
Aluminum in aluminum frame	–	1.32	0.99	0.93	0.79
Aluminum in aluminum frame with thermal break	–	1.13	0.80	0.74	0.63

a. Thermally broken sill (add 0.03 for non-thermally broken sill)
b. Non-thermally broken sill
c. Nominal U-factors are through the center of the insulated panel before consideration of thermal bridges around the edges of the door section and due to the frame.

TABLE A107.1(2)
DEFAULT U-FACTORS FOR REVOLVING DOORS

Revolving Doors	
Size (W x H)	**U-Factor**
3-wing	
8 ft x 7 ft	0.79
10 ft x 8 ft	0.80
4-wing	
7 ft x 6.5 ft	0.63
7 ft x 7.5 ft	0.64
Open	
82 in x 84 in	1.32

TABLE A107.1(3)
DEFAULT U-FACTORS FOR STEEL EMERGENCY DOORS

Double-Skin Steel Emergency Exit Doors		
Core Insulation	**3 ft x 6 ft 8 in**	**6 ft x 6 ft 8 in**
1-3/8 in. thickness		
Honeycomb kraft paper	0.57	0.52
Mineral wool, steel ribs	0.44	0.36
Polyurethane foam	0.34	0.28
1-3/4 in. thickness		
Honeycomb kraft paper	0.57	0.54
Mineral wool, steel ribs	0.41	0.33
Polyurethane foam	0.31	0.26
1-3/8 in. thickness		
Honeycomb kraft paper	0.60	0.55
Mineral wool, steel ribs	0.47	0.39
Polyurethane foam	0.37	0.31
1-3/4 in. thickness		
Honeycomb kraft paper	0.60	0.57
Mineral wool, steel ribs	0.44	0.37
Polyurethane foam	0.34	0.30

TABLE A107.1(4)
DEFAULT U-FACTORS FOR STEEL GARAGE AND HANGAR DOORS

Double-Skin Steel Garage and Aircraft Hangar Doors					
Insulation[e]	**One-piece tilt-up[a]**		**Sectional tilt-up[b]**	**Aircraft hangar**	
	8 ft. x 7 ft.	**16 ft. x 7 ft.**	**9 ft. x 7 ft.**	**72 ft. x 12 ft.[c]**	**240 ft. x 50 ft.[d]**
1-3/8 in. thickness					
EPS, steel ribs	0.36	0.33	0.34-0.39		
XPS, steel ribs	0.33	0.31	0.31-0.36		
2 in. thickness					
EPS, steel ribs	0.31	0.28	0.29-0.33		
XPS, steel ribs	0.29	0.26	0.27-0.31		
3 in. thickness					
EPS, steel ribs	0.26	0.23	0.25-0.28		
XPS, steel ribs	0.24	0.21	0.24-0.27		
4 in. thickness					
EPS, steel ribs	0.23	0.20	0.23-0.25		
XPS, steel ribs	0.21	0.19	0.21-0.24		
6 in. thickness					
EPS, steel ribs	0.20	0.16	0.20-0.21		
XPS, steel ribs	0.19	0.15	0.19-0.21		
4 in. thickness					
Non-insulated				1.10	1.23
Expanded polystyrene				0.25	0.16
Mineral wool, steel ribs				0.25	0.16
Extruded polystyrene				0.23	0.15
6 in. thickness					
Non-insulated				1.10	1.23
Expanded polystyrene				0.21	0.13
Mineral wool, steel ribs				0.23	0.13
Extruded polystyrene				0.20	0.12
Uninsulated					
All products	1.15				

a. Values are for thermally broken or thermally unbroken doors.
b. Lower values are for thermally broken doors; upper values are for doors with no thermal break.
c. Typical size for a small private airplane (single-engine or twin).
d. Typical hangar door for a midsize commercial jet airliner.
e. EPS is extruded polystyrene, XPS is expanded polystyrene.

SECTION A108
AIR INFILTRATION

A108.1 General. Tables A108.1(1) and A108.1(2) list effective air change rates and heat capacities for heat loss due to infiltration for Single-Family Residential.

The estimated seasonal average infiltration rate in air changes per hour (ACH) is given for standard air-leakage control (see Section R402.4 for air leakage requirements for Single-Family Residential). The effective air change rate shall be used in calculations for compliance under either the Component Performance or Systems Analysis approaches.

Heat loss due to infiltration shall be computed using the following equation:

$Q_{infil} = ACH_{eff} * HCP$

Where:

Q_{infil} = Heat loss due to air infiltration.

ACH_{eff} = The effective air infiltration rate in Table A108.1(1)

HCP = The Heat Capacity Density Product for the appropriate elevation or climate zone as given below.

TABLE A108.1(1)
ASSUMED EFFECTIVE AIR CHANGES PER HOUR

Air-Leakage Control Package	Air Changes per Hour	
	Natural	Effective
Standard	0.35	0.35

TABLE A108.1(2)
DEFAULT HEAT CAPACITY/DENSITY PRODUCT FOR AIR

Zone	Average Elevation	Heat Capacity/ Density
1	Mean Sea Level	0.0180 Btu/h•°F
2	2000	0.0168 Btu/h•°F
3	3000	0.0162 Btu/h•°F

Appendix B
DEFAULT INTERNAL LOAD VALUES AND SCHEDULES

SECTION B101
GENERAL

B101.1 Scope. The following default internal load values and schedules shall apply to Section C407.

SECTION B102
DEFAULT TABLES OF INTERNAL LOADS

B102 Default tables of internal loads. Default occupancy densities, receptacle power densities and service hot water consumption are included in Table B102.

TABLE B102
ACCEPTABLE OCCUPANCY DENSITIES, RECEPTACLE POWER DENSITIES AND SERVICE HOT WATER CONSUMPTION[a]

Building Type	Occupancy Density[b] ft^2/Person (Btu/h· ft^2)	Receptacle Power Density[c], Watts/ ft^2 (Btu/h· ft^2)	Service Hot Water Quantities[d] Btu/h per person
Assembly	50 (4.60)	0.25 (0.85)	215
Health/Institutional	200 (1.15)	1.00 (3.41)	135
Hotel/Motel	250 (0.92)	0.25 (0.85)	1,110
Light Manufacturing	750 (0.31)	0.20 (0.68)	225
Office	275 (0.84)	0.75 (2.56)	175
Parking Garage	NA	NA	NA
Restaurant	100 (2.30)	0.10)0.34)	390
Retail	300 (0.77)	0.25 (0.85)	135
School	75 (3.07)	0.50 (1.71)	215
Warehouse	15,000 (0.02)	0.10 (0.34)	225

a. The occupancy densities, receptacle power densities, and service hot water consumption values are from ASHRAE Standard 90.1-1989 and addenda.
b. Values are in square feet of conditioned floor area per person. Heat generation in Btu per person per hour is 230 sensible and 190 latent. Figures in parenthesis are equivalent Btu per hour per square foot.
c. Values are in Watts per square foot of conditioned floor area. Figures in parenthesis are equivalent Btu per hour per square foot. These values are the minimum acceptable. If other process loads are not input (such as for computers, cooking, refrigeration, etc.), it is recommended that receptacle power densities be increased until total process energy consumption is equivalent to 25% of the total.
d. Values are in Btu per person per hour.

SECTION B103
DEFAULT SCHEDULES

B103 Default schedules. Default schedules for occupancy, lighting, receptacles, HVAC, service hot water, and elevators are included in Tables B103(1) through B103(10).

TABLE B103(1)
ASSEMBLY OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	0	0	0	5	5	5	Off	Off	Off	0	0	0	0	0	0
2 (1-2 am)	0	0	0	5	5	5	Off	Off	Off	0	0	0	0	0	0
3 (2-3 am)	0	0	0	5	5	5	Off	Off	Off	0	0	0	0	0	0
4 (3-4 am)	0	0	0	5	5	5	Off	Off	Off	0	0	0	0	0	0
5 (4-5 am)	0	0	0	5	5	5	Off	Off	Off	0	0	0	0	0	0
6 (5-6 am)	0	0	0	5	5	5	On	Off	Off	0	0	0	0	0	0
7 (6-7 am)	0	0	0	40	5	5	On	On	On	0	0	0	0	0	0
8 (7-8 am)	0	0	0	40	30	30	On	On	On	0	0	0	0	0	0
9 (8-9 am)	20	20	10	40	30	30	On	On	On	0	0	0	0	0	0
10 (9-10 am)	20	20	10	75	50	30	On	On	On	5	5	5	0	0	0
11 (10-11 am)	20	20	10	75	50	30	On	On	On	5	5	5	0	0	0
12 (11-12 pm)	80	60	10	75	50	30	On	On	On	35	20	10	0	0	0
13 (12-1 pm)	80	60	10	75	50	65	On	On	On	5	0	0	0	0	0
14 (1-2 pm)	80	60	70	75	50	65	On	On	On	5	0	0	0	0	0
15 (2-3 pm)	80	60	70	75	50	65	On	On	On	5	0	0	0	0	0
16 (3-4 pm)	80	60	70	75	50	65	On	On	On	5	0	0	0	0	0
17 (4-5 pm)	80	60	70	75	50	65	On	On	On	5	0	0	0	0	0
18 (5-6 pm)	80	60	70	75	50	65	On	On	On	0	0	0	0	0	0
19 (6-7 pm)	20	60	70	75	50	65	On	On	On	0	0	0	0	0	0
20 (7-8 pm)	20	60	70	75	50	65	On	On	On	0	65	65	0	0	0
21 (8-9 pm)	20	60	70	75	50	65	On	On	On	0	30	30	0	0	0
22 (9-10 pm)	20	80	70	75	50	65	On	On	On	0	0	0	0	0	0
23 (10-11 pm)	10	10	20	25	50	5	On	On	On	0	0	0	0	0	0
24 (11-12 am)	0	0	0	5	5	5	Off	Off	Off	0	0	0	0	0	0
Total/Day	710	750	700	1155	800	845	1800	1700	1700	70	125	115	0	0	0
Total/Week		50.50 hours			74.20 hours			124 hours			5.9 hours				0 hours
Total/Year		2633 hours			3869 hours			6465 hours			308 hours				0 hours

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(2)
HEALTH OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
2 (1-2 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
3 (2-3 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
4 (3-4 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
5 (4-5 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
6 (5-6 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
7 (6-7 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
8 (7-8 am)	10	10	0	50	20	5	On	On	On	17	1	1	2	2	0
9 (8-9 am)	50	30	5	90	40	10	On	On	On	58	20	1	75	46	2
10 (9-10 am)	80	40	5	90	40	10	On	On	On	66	28	1	100	70	2
11 (10-11 am)	80	40	5	90	40	10	On	On	On	78	30	1	100	70	2
12 (11-12 pm)	80	40	5	90	40	10	On	On	On	82	30	1	100	70	2
13 (12-1 pm)	80	40	5	90	40	10	On	On	On	71	24	1	75	51	2
14 (1-2 pm)	80	40	5	90	40	10	On	On	On	82	24	1	100	51	2
15 (2-3 pm)	80	40	5	90	40	10	On	On	On	78	23	1	100	51	2
16 (3-4 pm)	80	40	5	90	40	10	On	On	On	74	23	1	100	51	2
17 (4-5 pm)	80	40	0	30	40	5	On	On	On	63	23	1	100	51	0
18 (5-6 pm)	50	10	0	30	40	5	On	On	On	41	10	1	100	25	0
19 (6-7 pm)	30	10	0	30	10	5	On	On	On	18	1	1	52	2	0
20 (7-8 pm)	30	0	0	30	10	5	On	On	On	18	1	1	52	0	0
21 (8-9 pm)	20	0	0	30	10	5	On	On	On	18	1	1	52	0	0
22 (9-10 pm)	20	0	0	30	10	5	On	On	On	10	1	1	28	0	0
23 (10-11 pm)	0	0	0	30	10	5	On	On	On	1	1	1	0	0	0
24 (11-12 am)	0	0	0	10	10	5	On	On	On	1	1	1	0	0	0
Total/Day	850	380	40	1060	550	160	2400	2400	2400	783	249	24	1136	540	16
Total/Week		46.70 hours			60.10 hours			168 hours			41.88 hours			62.36 hours	
Total/Year		2435 hours			3134 hours			8760 hours			2148 hours			3251 hours	

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(3)
HOTEL/MOTEL OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	90	90	70	20	20	30	On	On	On	20	20	25	40	44	55
2 (1-2 am)	90	90	70	15	20	30	On	On	On	15	15	20	33	35	55
3 (2-3 am)	90	90	70	10	10	20	On	On	On	15	15	20	33	35	43
4 (3-4 am)	90	90	70	10	10	20	On	On	On	15	15	20	33	35	43
5 (4-5 am)	90	90	70	10	10	20	On	On	On	20	20	20	33	35	43
6 (5-6 am)	90	90	70	20	10	20	On	On	On	25	25	30	33	35	43
7 (6-7 am)	70	70	70	40	30	30	On	On	On	50	40	50	42	40	52
8 (7-8 am)	40	50	70	50	30	40	On	On	On	60	50	50	42	32	52
9 (8-9 am)	40	50	50	40	40	40	On	On	On	55	50	50	52	45	65
10 (9-10 am)	20	30	50	40	40	30	On	On	On	45	50	55	52	45	65
11 (10-11 am)	20	30	50	25	30	30	On	On	On	40	45	50	40	42	53
12 (11-12 pm)	20	30	30	25	25	30	On	On	On	45	50	50	51	60	60
13 (12-1 pm)	20	30	30	25	25	30	On	On	On	40	50	40	51	65	53
14 (1-2 pm)	20	30	20	25	25	20	On	On	On	35	45	40	51	65	51
15 (2-3 pm)	20	30	20	25	25	20	On	On	On	30	40	30	51	65	50
16 (3-4 pm)	30	30	20	25	25	20	On	On	On	30	40	30	51	65	44
17 (4-5 pm)	50	30	30	25	25	20	On	On	On	30	35	30	63	65	64
18 (5-6 pm)	50	50	40	25	25	20	On	On	On	40	40	40	80	75	62
19 (6-7 pm)	50	60	40	60	60	50	On	On	On	55	55	50	86	80	65
20 (7-8 pm)	70	60	60	80	70	70	On	On	On	60	55	50	70	80	63
21 (8-9 pm)	70	60	60	90	70	80	On	On	On	50	50	40	70	75	63
22 (9-10 pm)	80	70	80	80	70	60	On	On	On	55	55	50	70	75	63
23 (10-11 pm)	90	70	80	60	60	50	On	On	On	45	40	40	45	55	40
24 (11-12 am)	90	70	80	30	30	30	On	On	On	25	30	20	45	55	40
Total/Day	1390	1390	1300	855	785	810	2400	2400	2400	915	930	900	1217	1303	1287
Total/Week		96.40 hours			58.70 hours			168.0 hours			64.05 hours			86.75 hours	
Total/Year		5026 hours			3061 hours			8760 hours			3340 hours			4523 hours	

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(4)
LIGHT MANUFACTURING OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
2 (1-2 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
3 (2-3 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
4 (3-4 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
5 (4-5 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
6 (5-6 am)	0	0	0	10	5	5	Off	Off	Off	8	8	7	0	0	0
7 (6-7 am)	10	10	5	10	10	5	On	On	Off	7	7	4	0	0	0
8 (7-8 am)	20	10	5	30	10	5	On	On	Off	19	11	4	35	16	0
9 (8-9 am)	95	30	5	90	30	5	On	On	Off	35	15	4	69	14	0
10 (9-10 am)	95	30	5	90	30	5	On	On	Off	38	21	4	43	21	0
11 (10-11 am)	95	30	5	90	30	5	On	On	Off	39	19	4	37	18	0
12 (11-12 pm)	95	30	5	90	30	5	On	On	Off	47	23	6	43	25	0
13 (12-1 pm)	50	10	5	80	15	5	On	On	Off	57	20	6	58	21	0
14 (1-2 pm)	95	10	5	90	15	5	On	On	Off	54	19	9	48	13	0
15 (2-3 pm)	95	10	5	90	15	5	On	On	Off	34	15	6	37	8	0
16 (3-4 pm)	95	10	5	90	15	5	On	On	Off	33	12	4	37	4	0
17 (4-5 pm)	95	10	5	90	15	5	On	On	Off	44	14	4	46	5	0
18 (5-6 pm)	30	5	5	50	5	5	On	On	Off	26	7	4	62	6	0
19 (6-7 pm)	10	5	0	30	5	5	On	Off	Off	21	7	4	20	0	0
20 (7-8 pm)	10	0	0	30	5	5	On	Off	Off	15	7	4	12	0	0
21 (8-9 pm)	10	0	0	20	5	5	On	Off	Off	17	7	4	4	0	0
22 (9-10 pm)	10	0	0	20	5	5	On	Off	Off	8	9	7	4	0	0
23 (10-11 pm)	5	0	0	10	5	5	Off	Off	Off	5	5	4	0	0	0
24 (11-12 am)	5	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
Total/Day	920	200	60	1040	280	120	1600	1200	0	537	256	113	555	151	0
Total/Week		48.60 hours			56.00 hours			92.00 hours			30.54 hours			29.26 hours	
Total/Year		2534 hours			2920 hours			4797 hours			1592 hours			1526 hours	

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(5)
OFFICE OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
2 (1-2 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
3 (2-3 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
4 (3-4 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
5 (4-5 am)	0	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
6 (5-6 am)	0	0	0	10	5	5	Off	Off	Off	8	8	7	0	0	0
7 (6-7 am)	10	10	5	10	10	5	On	On	Off	7	7	4	0	0	0
8 (7-8 am)	20	10	5	30	10	5	On	On	Off	19	11	4	35	16	0
9 (8-9 am)	95	30	5	90	30	5	On	On	Off	35	15	4	69	14	0
10 (9-10 am)	95	30	5	90	30	5	On	On	Off	38	21	4	43	21	0
11 (10-11 am)	95	30	5	90	30	5	On	On	Off	39	19	4	37	18	0
12 (11-12 pm)	95	30	5	90	30	5	On	On	Off	47	23	6	43	25	0
13 (12-1 pm)	50	10	5	80	15	5	On	On	Off	57	20	6	58	21	0
14 (1-2 pm)	95	10	5	90	15	5	On	On	Off	54	19	9	48	13	0
15 (2-3 pm)	95	10	5	90	15	5	On	On	Off	34	15	6	37	8	0
16 (3-4 pm)	95	10	5	90	15	5	On	On	Off	33	12	4	37	4	0
17 (4-5 pm)	95	10	5	90	15	5	On	On	Off	44	14	4	46	5	0
18 (5-6 pm)	30	5	5	50	5	5	On	On	Off	26	7	4	62	6	0
19 (6-7 pm)	10	5	0	30	5	5	On	Off	Off	21	7	4	20	0	0
20 (7-8 pm)	10	0	0	30	5	5	On	Off	Off	15	7	4	12	0	0
21 (8-9 pm)	10	0	0	20	5	5	On	Off	Off	17	7	4	4	0	0
22 (9-10 pm)	10	0	0	20	5	5	On	Off	Off	8	9	7	4	0	0
23 (10-11 pm)	5	0	0	10	5	5	Off	Off	Off	5	5	4	0	0	0
24 (11-12 am)	5	0	0	5	5	5	Off	Off	Off	5	5	4	0	0	0
Total/Day	920	200	60	1040	280	120	1600	1200	0	537	256	113	555	151	0
Total/Week		48.60 hours			56.00 hours			92.00 hours			30.54 hours			29.26 hours	
Total/Year		2534 hours			2920 hours			4797 hours			1592 hours			1526 hours	

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(6)
PARKING GARAGE OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)				100	100	100									
2 (1-2 am)				100	100	100									
3 (2-3 am)				100	100	100									
4 (3-4 am)				100	100	100									
5 (4-5 am)				100	100	100									
6 (5-6 am)				100	100	100									
7 (6-7 am)				100	100	100									
8 (7-8 am)				100	100	100									
9 (8-9 am)				100	100	100									
10 (9-10 am)				100	100	100									
11 (10-11 am)				100	100	100									
12 (11-12 pm)	NA			100	100	100	Based on likely use			NA			Included with other occupancies		
13 (12-1 pm)				100	100	100									
14 (1-2 pm)				100	100	100									
15 (2-3 pm)				100	100	100									
16 (3-4 pm)				100	100	100									
17 (4-5 pm)				100	100	100									
18 (5-6 pm)				100	100	100									
19 (6-7 pm)				100	100	100									
20 (7-8 pm)				100	100	100									
21 (8-9 pm)				100	100	100									
22 (9-10 pm)				100	100	100									
23 (10-11 pm)				100	100	100									
24 (11-12 am)				100	100	100									
Total/Day				2400	2400	2400									
Total/Week						168 hours									
Total/Year						8760 hours									

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(7)
RESTAURANT OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	15	30	20	15	20	20	On	On	On	20	20	25	0	0	0
2 (1-2 am)	15	25	20	15	15	15	On	On	On	15	15	20	0	0	0
3 (2-3 am)	5	5	5	15	15	15	On	On	On	15	15	20	0	0	0
4 (3-4 am)	0	0	0	15	15	15	Off	Off	Off	0	0	0	0	0	0
5 (4-5 am)	0	0	0	15	15	15	Off	Off	Off	0	0	0	0	0	0
6 (5-6 am)	0	0	0	20	15	15	Off	Off	Off	0	0	0	0	0	0
7 (6-7 am)	0	0	0	40	30	30	Off	Off	Off	0	0	0	0	0	0
8 (7-8 am)	5	0	0	40	30	30	On	Off	Off	60	0	0	0	0	0
9 (8-9 am)	5	0	0	60	60	50	On	Off	Off	55	0	0	0	0	0
10 (9-10 am)	5	5	0	60	60	50	On	On	Off	45	50	0	0	0	0
11 (10-11 am)	20	20	10	90	80	70	On	On	On	40	45	50	0	0	0
12 (11-12 pm)	50	45	20	90	80	70	On	On	On	45	50	50	0	0	0
13 (12-1 pm)	80	50	25	90	80	70	On	On	On	40	50	40	0	0	0
14 (1-2 pm)	70	50	25	90	80	70	On	On	On	35	45	40	0	0	0
15 (2-3 pm)	40	35	15	90	80	70	On	On	On	30	40	30	0	0	0
16 (3-4 pm)	20	30	20	90	80	70	On	On	On	30	40	30	0	0	0
17 (4-5 pm)	25	30	25	90	80	60	On	On	On	30	35	30	0	0	0
18 (5-6 pm)	50	30	35	90	90	60	On	On	On	40	40	40	0	0	0
19 (6-7 pm)	80	70	55	90	90	60	On	On	On	55	55	50	0	0	0
20 (7-8 pm)	80	90	65	90	90	60	On	On	On	60	55	50	0	0	0
21 (8-9 pm)	80	70	70	90	90	60	On	On	On	50	50	40	0	0	0
22 (9-10 pm)	50	65	35	90	90	60	On	On	On	55	55	50	0	0	0
23 (10-11 pm)	35	55	20	50	50	50	On	On	On	45	40	40	0	0	0
24 (11-12 am)	20	35	20	30	30	30	On	On	On	25	30	20	0	0	0
Total/Day	750	740	485	1455	1365	1115	2000	1800	1700	790	730	625	0	0	0
Total/Week		49.75 hours			97.55 hours			135 hours			53.05 hours				0 hours
Total/Year		2594 hours			5086 hours			7039 hours			2766 hours				0 hours

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(8)
RETAIL OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	0	0	0	5	5	5	Off	Off	Off	4	11	7	0	0	0
2 (1-2 am)	0	0	0	5	5	5	Off	Off	Off	5	10	7	0	0	0
3 (2-3 am)	0	0	0	5	5	5	Off	Off	Off	5	8	7	0	0	0
4 (3-4 am)	0	0	0	5	5	5	Off	Off	Off	4	6	6	0	0	0
5 (4-5 am)	0	0	0	5	5	5	Off	Off	Off	4	6	6	0	0	0
6 (5-6 am)	0	0	0	5	5	5	Off	Off	Off	4	6	6	0	0	0
7 (6-7 am)	0	0	0	5	5	5	On	On	Off	4	7	7	0	0	0
8 (7-8 am)	10	10	0	20	10	5	On	On	Off	15	20	10	12	9	0
9 (8-9 am)	20	20	0	50	30	10	On	On	On	23	24	12	22	21	0
10 (9-10 am)	50	50	10	90	60	10	On	On	On	32	27	14	64	56	11
11 (10-11 am)	50	60	20	90	90	40	On	On	On	41	42	29	74	66	13
12 (11-12 pm)	70	80	20	90	90	40	On	On	On	57	54	31	68	68	35
13 (12-1 pm)	70	80	40	90	90	60	On	On	On	62	59	36	68	68	37
14 (1-2 pm)	70	80	40	90	90	60	On	On	On	61	60	36	71	69	37
15 (2-3 pm)	70	80	40	90	90	60	On	On	On	50	49	34	72	70	39
16 (3-4 pm)	80	80	40	90	90	60	On	On	On	45	48	35	72	69	41
17 (4-5 pm)	70	80	40	90	90	60	On	On	On	46	47	37	73	66	38
18 (5-6 pm)	50	60	20	90	90	40	On	On	Off	47	46	34	68	58	34
19 (6-7 pm)	50	20	10	60	50	20	On	On	Off	42	44	25	68	47	3
20 (7-8 pm)	30	20	0	60	30	5	On	On	Off	34	36	27	58	43	0
21 (8-9 pm)	30	20	0	50	30	5	On	On	Off	33	29	21	54	43	0
22 (9-10 pm)	0	10	0	20	10	5	Off	On	Off	23	22	16	0	8	0
23 (10-11 pm)	0	0	0	5	5	5	Off	Off	Off	13	16	10	0	0	0
24 (11-12 am)	0	0	0	5	5	5	Off	Off	Off	8	13	6	0	0	0
Total/Day	720	750	280	1115	985	525	1500	1600	900	662	690	459	844	761	288
Total/Week		46.30 hours			70.85 hours			100 hours			44.59 hours			52.69 hours	
Total/Year		2414 hours			3694 hours			5214 hours			2325 hours			2747 hours	

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(9)
SCHOOL OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	0	0	0	5	5	5	Off	Off	Off	5	3	3	0	0	0
2 (1-2 am)	0	0	0	5	5	5	Off	Off	Off	5	3	3	0	0	0
3 (2-3 am)	0	0	0	5	5	5	Off	Off	Off	5	3	3	0	0	0
4 (3-4 am)	0	0	0	5	5	5	Off	Off	Off	5	3	3	0	0	0
5 (4-5 am)	0	0	0	5	5	5	Off	Off	Off	5	3	3	0	0	0
6 (5-6 am)	0	0	0	5	5	5	Off	Off	Off	5	3	3	0	0	0
7 (6-7 am)	0	0	0	5	5	5	Off	Off	Off	5	3	3	0	0	0
8 (7-8 am)	5	0	0	30	5	5	On	Off	Off	10	3	3	0	0	0
9 (8-9 am)	75	10	0	85	15	5	On	On	Off	34	3	5	30	0	0
10 (9-10 am)	90	10	0	95	15	5	On	On	Off	60	5	5	30	0	0
11 (10-11 am)	90	10	0	95	15	5	On	On	Off	63	5	5	30	0	0
12 (11-12 pm)	80	10	0	95	15	5	On	On	Off	72	5	5	30	0	0
13 (12-1 pm)	80	10	0	80	15	5	On	On	Off	79	5	5	30	0	0
14 (1-2 pm)	80	0	0	80	5	5	On	Off	Off	83	3	5	30	0	0
15 (2-3 pm)	80	0	0	80	5	5	On	Off	Off	61	3	3	30	0	0
16 (3-4 pm)	45	0	0	70	5	5	On	Off	Off	65	3	3	15	0	0
17 (4-5 pm)	15	0	0	50	5	5	On	Off	Off	10	3	3	0	0	0
18 (5-6 pm)	5	0	0	50	5	5	On	Off	Off	10	3	3	0	0	0
19 (6-7 pm)	15	0	0	35	5	5	On	Off	Off	19	3	3	0	0	0
20 (7-8 pm)	20	0	0	35	5	5	On	Off	Off	25	3	3	0	0	0
21 (8-9 pm)	20	0	0	35	5	5	On	Off	Off	22	3	3	0	0	0
22 (9-10 pm)	10	0	0	30	5	5	On	Off	Off	22	3	3	0	0	0
23 (10-11 pm)	0	0	0	5	5	5	Off	Off	Off	12	3	3	0	0	0
24 (11-12 am)	0	0	0	5	5	5	Off	Off	Off	9	3	3	0	0	0
Total/Day	710	50	0	990	170	120	1500	500	0	691	80	84	285	0	0
Total/Week		36.00 hours			52.40 hours			80.00 hours			36.19 hours			14.25 hours	
Total/Year		1877 hours			2732 hours			4171 hours			1887 hours			743 hours	

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

TABLE B103(10)
WAREHOUSE OCCUPANCY[a]

Hour of Day (Time)	Schedule for Occupancy Percent of Maximum Load			Schedule for Lighting Receptacle Percent of Maximum Load			Schedule for HVAC System			Schedule for Service Hot Water Percent of Maximum Load			Schedule for Elevator Percent of Maximum Load		
	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun	Wk	Sat	Sun
1 (12-1 am)	0	0	0	5	5	5	Off	Off	Off	2	2	2	0	0	0
2 (1-2 am)	0	0	0	5	5	5	Off	Off	Off	2	2	2	0	0	0
3 (2-3 am)	0	0	0	5	5	5	Off	Off	Off	2	2	2	0	0	0
4 (3-4 am)	0	0	0	5	5	5	Off	Off	Off	2	2	2	0	0	0
5 (4-5 am)	0	0	0	5	5	5	Off	Off	Off	5	2	2	0	0	0
6 (5-6 am)	0	0	0	5	5	5	Off	Off	Off	7	2	2	0	0	0
7 (6-7 am)	0	0	0	5	5	5	Off	Off	Off	7	2	2	0	0	0
8 (7-8 am)	15	0	0	40	5	5	On	Off	Off	10	2	2	0	0	0
9 (8-9 am)	70	20	0	70	8	5	On	On	Off	30	6	2	0	0	0
10 (9-10 am)	90	20	0	90	24	5	On	On	Off	36	12	2	0	0	0
11 (10-11 am)	90	20	0	90	24	5	On	On	Off	36	12	2	30	0	0
12 (11-12 pm)	90	20	0	90	24	5	On	On	Off	46	17	2	0	0	0
13 (12-1 pm)	50	10	0	80	5	5	On	On	Off	57	4	4	0	0	0
14 (1-2 pm)	85	10	0	90	5	5	On	On	Off	43	4	4	0	0	0
15 (2-3 pm)	85	10	0	90	5	5	On	On	Off	38	2	2	0	0	0
16 (3-4 pm)	85	10	0	90	5	5	On	On	Off	40	2	2	40	0	0
17 (4-5 pm)	20	0	0	90	5	5	On	Off	Off	30	2	2	0	0	0
18 (5-6 pm)	0	0	0	30	5	5	Off	Off	Off	18	2	2	0	0	0
19 (6-7 pm)	0	0	0	5	5	5	Off	Off	Off	3	2	2	0	0	0
20 (7-8 pm)	0	0	0	5	5	5	Off	Off	Off	3	2	2	0	0	0
21 (8-9 pm)	0	0	0	5	5	5	Off	Off	Off	3	2	2	0	0	0
22 (9-10 pm)	0	0	0	5	5	5	Off	Off	Off	3	2	2	0	0	0
23 (10-11 pm)	0	0	0	5	5	5	Off	Off	Off	3	2	2	0	0	0
24 (11-12 am)	0	0	0	5	5	5	Off	Off	Off	3	2	2	0	0	0
Total/Day	680	120	0	915	180	120	1000	800	0	429	91	52	70	0	0
Total/Week		35.20 hours			48.75 hours			58.00 hours			22.88 hours			3.50 hours	
Total/Year		1835 hours			2542 hours			3024 hours			1193 hours			182 hours	

Wk = Weekday

a. Schedules for occupancy, lighting, receptacle, HVAC system, and service hot water are from ASHRAE Standard 90.1-1989 and addendums, except that 5% emergency lighting has been added for all off hours. Elevator schedules, except for restaurants, are from the U.S. Department of Energy Standard Evaluation Techniques except changed to 0% when occupancy is 0%. **These values may be used only if actual schedules are not known.**

APPENDIX C

EXTERIOR DESIGN CONDITIONS

As required by Sections C302.2 and R302.2, the heating or cooling outdoor design temperatures shall be selected from Table C-1.

TABLE C-1
OUTDOOR DESIGN TEMPERATURES

Location	Outdoor Design Temp Heating (°F)	Outdoor Design Temp Cooling (°F)
Aberdeen 20NNE	25	83
Anacortes	24	72
Anatone	-4	89
Auburn	25	84
Battleground	19	91
Bellevue	24	83
Bellingham 2N	19	78
Blain	17	73
Bremerton	29	83
Burlington	19	77
Chehalis	21	87
Chelan	10	89
Cheney	4	94
Chesaw	-11	81
Clarkston	10	94
Cle Elum	1	91
Colfax 1NW	2	94
Colville AP	-2	92
Concrete	19	83
Connell 4NNW	6	100
Cougar 5E	25	93
Dallesport AP	14	99
Darrington RS	13	85
Davenport	5	92
Edmonds	24	82
Ellensburg AP	2	90
Elma	24	88
Ephrata AP	7	97
Everett Paine AFB	21	79
Forks 1E	23	81
Glacier RS	13	82
Glenoma (Kosmos)	18	89
Goldendale	7	94
Grays River Hatchery	24	86

Location	Outdoor Design Temp Heating (°F)	Outdoor Design Temp Cooling (°F)
Greenwater	1.4	84
Grotto	21	84
Hoquiam AP	26	79
Inchelium 2NW	0	92
John Day Dam	19	100
Long Beach 3NNE	25	77
Longview	24	87
Lower Granite Dam	14	98
Lower Monument Dam	18	103
Marysville	23	79
Metaline Falls	-1	89
Methow 2W	1	89
Nespelem 2S	-4	93
Newhalem	19	89
Newport	-5	92
Northport	2	92
Oak Harbor	16	74
Odessa	7	100
Olga 2SE	24	71
Olympia AP	17	85
Omak 2NW	3	90
Oroville	5	93
Othello	9	98
Packwood	16	90
Plain	-3	89
Pleasant View	16	98
Pomeroy	3	95
Port Angeles	28	75
Port Townsend	25	76
Prosser	12	97
Puyallup	19	86
Quilcene 2SW	23	83
Quinault RS	25	84

Location	Outdoor Design Temp Heating (°F)	Outdoor Design Temp Cooling (°F)
Rainier, Longmire	15	85
Paradise RS	8	71
Raymond	28	81
Redmond	17	83
Republic	-9	87
Richland	11	101
Ritzville	6	99
Satus Pass	10	90
Seattle: SeaTac AP	24	83
Sedro Woolley 1E	19	78
Sequim	23	78
Shelton	23	85
Smyrna	8	102
Snohomish	21	81
Snoqualmie Pass	6	80
Spokane AP	4	92
Spokane CO	10	96
Stampede Pass	7	76
Stehekin 3 NW	12	85
Stevens Pass	6	77
Tacoma CO	29	82
Tatoosh Island	31	63
Toledo AP	17	84
Vancouver	22	88
Vashon Island	28	78
Walla Walla AP	6	96
Waterville	1	88
Wellpinit	1	93
Wenatchee CO	10	92
Whidbey Island	11	71
Willapa Harbor	26	81
Wilson Creek	3	96
Winthrop 1WSW	-12	91
Yakima AP	11	94

ABBREVIATIONS: AFB Air Force Base AP Airport CO City Office RS Ranger Station
Typical: "4(miles)NE"